						ENT OF N	OF UTAH IATURAL RES ., GAS AND I				AMEN	FO IDED REPO	RM 3	
		APP	LICATION F	OR	PERMIT TO DE	RILL				1. WELL NAME and		<b>R</b> 2-36G4BS		
2. TYPE (	OF WORK	RILL NEW WELL (	REENTER	R P&	A WELL D	EEPEN WEL	ш 🗀			3. FIELD OR WILDO		L BUTTES		
4. TYPE (										5. UNIT or COMMU			EEMENT	NAME
6. NAME	OF OPERATOR	<b>R</b>			ed Methane Well: I					7. OPERATOR PHO	NE	L BUTTES 29-6515		
8. ADDRI	ESS OF OPERA	TOR			GAS ONSHORE, L.P	•				9. OPERATOR E-MA	IL			
	RAL LEASE N	JMBER	7.U. BOX 1/3//	9, D	enver, CO, 80217 11. MINERAL O	WNERSHI	P			12. SURFACE OWNI		@anadarko	com	
	L, INDIAN, OF	ML-22650			FEDERAL (	INDIAN	STATE (	FEE	$\bigcirc$		DIAN 🛑	•	_	FEE 🔵
13. NAMI	E OF SURFACE	OWNER (if box :	12 = 'fee')							14. SURFACE OWNI	ER PHO	NE (if box	12 = 'fe	ee')
15. ADDI	RESS OF SURF	ACE OWNER (if b	ox 12 = 'fee')							16. SURFACE OWN	ER E-MA	AIL (if box	12 = 'fe	ee')
	AN ALLOTTEE 2 = 'INDIAN')	OR TRIBE NAME			18. INTEND TO MULTIPLE FORM	AATIONS	GLE PRODUCT		_	19. SLANT  VERTICAL DIR	RECTION	Δι 📵 Ι	HORIZON	JTAI ( )
20. LOCATION OF WELL F					OTAGES		TR-QTR	SECT		TOWNSHIP		ANGE	_	RIDIAN
	ON AT SURFAC		240		NL 2441 FEL		SWNE	36		9.0 S		2.0 E	-	S
Top of U	Ippermost Pro	ducing Zone	223	5 FN	NL 1818 FEL	_	SWNE	36	5	9.0 S	2	2.0 E	+	S
At Total	Depth		223	5 FN	NL 1818 FEL		SWNE	36	5	9.0 S	2	2.0 E		
21. COU	NTY	UINTAH			22. DISTANCE T		ST LEASE LIN	IE (Feet)		23. NUMBER OF AC		DRILLING	UNIT	
		OINTAIT			25. DISTANCE T	O NEARES	ST WELL IN S	SAME POO	L	26. PROPOSED DEP		40		
22 5151		IND 151/51			(Applied For Dri		493				: 8760	TVD: 867	8	
27. ELEV	ATION - GROU	4959			28. BOND NUME		013542			29. SOURCE OF DRI WATER RIGHTS AP	PROVAI		IF APP	LICABLE
							Cement Inf		n					
String Surf	Hole Size	Casing Size 8.625	0 - 2280		3	& Thread  5 LT&C	Max Mu			Type V		Sacks 180	Yield 1.15	Weight 15.8
Juii	- 11	0.023	0 2200		0.0 333	LIGC				Class G		270	1.15	15.8
Prod	7.875	4.5	0 - 8760	1	1.5 I-80	LT&C	12.	.5	Pren	nium Lite High Stre	ngth	280	3.38	11.0
										50/50 Poz		1190	1.31	14.3
						ATTAC	HMENTS							
	VERIFY T	HE FOLLOWIN	G ARE ATTA	СН	ED IN ACCORD	DANCE W	ITH THE U	TAH OIL	AND (	GAS CONSERVATI	ON GE	NERAL R	ULES	
<b>✓</b> w	ELL PLAT OR	MAP PREPARED E	BY LICENSED S	SUR	VEYOR OR ENGI	NEER	<b>№</b> сом	IPLETE DR	ILLING	PLAN				
AF	FIDAVIT OF S	TATUS OF SURFA	CE OWNER A	GRE	EMENT (IF FEE S	URFACE)	FOR	M 5. IF OP	ERATO	R IS OTHER THAN TI	HE LEAS	SE OWNER		
DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY						<b>№</b> торо	OGRAPHIC	CAL MAI	P					
<b>NAME</b> G	ina Becker			T2	ITLE Regulatory A	nalyst II			PHON	<b>E</b> 720 929-6086				
SIGNAT	URE			D.	<b>ATE</b> 05/13/2011				EMAIL	gina.becker@anadarl	ko.com			
	MBER ASSIGN 047516270			A	PPROVAL			,	Bo	00 gjill				
								Perr	nit Manager					

NBU 922-36G3 Pad Drilling Program
1 of 4

#### Kerr-McGee Oil & Gas Onshore, L.P.

#### NBU 922-36G4BS

Surface: 2405 FNL / 2441 FEL SWNE BHL: 2235 FNL / 1818 FEL SWNE

Section 36 T9S R22E

Unitah County, Utah Mineral Lease: ML-22650

#### **ONSHORE ORDER NO. 1**

#### **DRILLING PROGRAM**

## 1. & 2. <u>Estimated Tops of Important Geologic Markers</u>: <u>Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations</u>:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1161	
Birds Nest	1448	Water
Mahogany	1826	Water
Wasatch	4249	Gas
Mesaverde	6462	Gas
MVU2	7474	Gas
MVL1	8033	Gas
TVD	8678	
TD	8760	

#### 3. <u>Pressure Control Equipment</u> (Schematic Attached)

Please refer to the attached Drilling Program

#### 4. <u>Proposed Casing & Cementing Program:</u>

Please refer to the attached Drilling Program

#### 5. <u>Drilling Fluids Program</u>:

Please refer to the attached Drilling Program

#### 6. <u>Evaluation Program</u>:

Please refer to the attached Drilling Program

NBU 922-36G3 Pad Drilling Program 2 of 4

#### 7. Abnormal Conditions:

Maximum anticipated bottom hole pressure calculated at 8678' TVD, approximately equals 5,727 psi 0.64 psi/ft = actual bottomhole gradient

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,633 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

#### **8.** Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

#### 9. <u>Variances:</u>

Please refer to the attached Drilling Program. Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- · Blowout Prevention Equipment (BOPE) requirements;
- Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

#### Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

NBU 922-36G3 Pad Drilling Program 3 of 4

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 11 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

#### Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

#### Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

#### Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and

NBU 922-36G3 Pad Drilling Program 4 of 4

on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

#### Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.


#### **Other Information:**

Please refer to the attached Drilling Program.



# KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

COMPANY NAME KERR-McGEE OIL & GAS ONSHORE LP DATE May 6, 2011 NBU 922-36G4BS WELL NAME TD 8,678' TVD 8,760' MD **FIELD** Natural Buttes **COUNTY** Uintah STATE Utah FINISHED ELEVATION 4959.2 SURFACE LOCATION SWNE 2405 FNL 2441 FEL Sec 36 T 9S Latitude: 39.993205 Longitude: -109.386924 NAD 27 BTM HOLE LOCATION SWNE 1818 FEL 2235 FNL Sec 36 T 9S R 22E Latitude: 39.993662 -109.384704 NAD 27 Longitude: OBJECTIVE ZONE(S) Wasatch/Mesaverde





#### **KERR-McGEE OIL & GAS ONSHORE LP**

#### **DRILLING PROGRAM**

CASING PROGRAM	<u>1</u>								DESIGN I	ACTORS	
										LTC	BTC
	SIZE	INT	ERVAL		WT.	GR.	CPLG.	BURST	COLLA	PSE	TENSION
CONDUCTOR	14"		0-40'								
								3,390	1,880	348,000	N/A
SURFACE	8-5/8"	0	to	2,280	28.00	IJ-55	LTC	2.37	1.76	6.22	N/A
								7,780	6,350	279,000	367,000
PRODUCTION	4-1/2"	0	to	8,760	11.60	I-80	LTC/BTC	1.11	1.13	3.39	4.46

**Surface Casing:** 

(Burst Assumptions: TD = 12.5 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi) 0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

#### **CEMENT PROGRAM**

	FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT		YIELD			
SURFACE LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80		1.15			
Option 1		+ 0.25 pps flocele								
TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80		1.15			
		+ 2% CaCl + 0.25 pps flocele								
SURFACE		NOTE: If well will circulate water to surface, option 2 will be utilized								
Option 2 LEAD	1,780'	65/35 Poz + 6% Gel + 10 pps gilsonite	160	35%	11.00		3.82			
		+ 0.25 pps Flocele + 3% salt BWOW								
TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80		1.15			
		+ 0.25 pps flocele								
TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80		1.15			
PRODUCTION LEAD	3,740'	Premium Lite II +0.25 pps	280	20%	11.00		3.38			
		celloflake + 5 pps gilsonite + 10% gel								
		+ 0.5% extender								
TAIL	5,020'	50/50 Poz/G + 10% salt + 2% gel	1,190	35%	14.30		1.31			
		+ 0.1% R-3								

<sup>\*</sup>Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

#### **FLOAT EQUIPMENT & CENTRALIZERS**

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

#### ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.


BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.
Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.


DRILLING ENGINEER:		DATE:
	Nick Spence / Emile Goodwin	
DRILLING SUPERINTENDENT:		DATE:
	Kenny Cathings / Lovel Young	

<sup>\*</sup>Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

EXHIBIT A NBU 922-36G4BS



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK



			RFACE POSITIO		BOTTOM HOLE					
WELL NAME	NAD83			D27	F06715-	NAI		NAC	F067/ 5	
NBU	<b>LATITUDE</b> 39°59'35.125"	LONGITUDE	<b>LATITUDE</b> 39°59'35.249"	LONGITUDE	FOOTAGES	39°59'33.789"	LONGITUDE	<b>LATITUDE</b> 39°59'33.913"	LONGITUDE	
NBU 922-36G4CS	39.993090°	109°23'15.457" 109.387627°	39-59-35.249" 39.993125°	109°23'13.005" 109.386946°	2434' FNL 2447' FEL	39.59.33.789° 39.992719°	109°23'07.372" 109.385381°	39.992754°	109°23'04.921" 109.384700°	2566' FNL 1818' FEL
NBU	39°59'35.221"	109°23'15.431"	39°59'35.345"	109°23'12.979"	2424' FNL	39°59'35.472"	109°23'24.214"	39°59'35.596"	109°23'21.762"	2401' FNL
022-36F4CS	39.993117°	109.387620°	39.993152°	109.386939°	2445' FEL	39.993187°	109.390059°	39.993221°	109.389378°	2149' FWI
NBU 122-36F4BS	39°59'35.318" 39.993144°	109°23'15.405" 109.387612°	39°59'35.442" 39.993178°	109°23'12.953" 109.386931°	2414' FNL 2443' FEL	39°59'38.742" 39.994095°	109°23'24.216" 109.390060°	39°59'38.866" 39.994130°	109°23'21.765"  109.389379°	2070' FNL 2149' FWI
NBU	39°59'35.415"		39°59'35.539"	109°23'12.927"	2405' FNL	39°59'37.059"	109°23'07.386"	39°59'37.183"	109:30937 9 109°23'04.935"	
922-36G4BS	39.993171°	109.387605°	39.993205°	109.386924°	2441' FEL	39.993628°	109.385385°	39.993662°	109.384704°	1818' FEL
NBU 922-36G	39°59'34.763" 39.992990°	109°23'15.667" 109.387685°	39°59'34.887" 39.993024°	109°23'13.216" 109.387004°	2471 FNL 2463 FEL					
722-30G	33.332330	109.307003		COORDINATES -		Position to Rott	om Hole			
WELL NAME	NORTH	EAST WE		ORTH EAS		NAME NOR		WELL NAM	IE NORTH	EAST
NBU	-134.6	629 51 NBU	J ,	24.81 -683.	NBU	346		NBU	167.0'	622.11
922-36G4CS	151.0	922	-36F4CS	003.	922-36	6F4BS	.0 000.5	922-36G4B	s   107.0	022.1
,09	S C A L I		N N		N11°40'52"E		BASIS OF BEAR THE NE ¼ OF SI S.L.B.&M. WHI GLOBAL POSIT OBSERVATION	ECTION 36, TO CH IS TAKEN TONING SATE	9S, R22E, FROM Ellite	
<b>⊸</b>	$I_{-}I_{-}I_{-}I_{-}I_{-}I_{-}I_{-}I_{-}$	Az=272.0 (To Bottom 87°55'29"W	7528° / Hole) /		P NÉ	SU 922-36C U 922-36F4 J 922-36F4	AZ= (TO B (TO B N74°5 G4BS Az. to Exist BS Az. to Exist CS Az. to Exist	st. W.H.=199.9 t. W.H.=201.6	5.77611° 69.7' 96056° 59.8' 1528° 49.9'	
					EXISTIN NBU 92		S77°55'4 (To Bot Az=102	70"E - 643.7 tom Hole) 2.07222°	8'	
WELL	8th Street - De L PAD - N PAD INTE	& Gas Ons enver, Colorado NBU 922-3 ERFERENCE 4CS, NBU 92	6G3 PLAT	CONS	609 ULTING, LL	E .	MBERL ENGINEERIN 209 NORTH 3	G & LAND 300 West - Ver	SURVEYINC RNAL, UTAH 84	,
		NBU 922-36			orth Main Stre	et 09-0		SURVEYED B	or: M.S.B.	
		TON 36, T9S,	, III		an WY 8280:	ı    DAT	E DRAWN:	DRAWN BY:	B.M.	5
		H COUNTY, I			307-674-060	9		Date Last Rev		•
J.L.D.CX	, OHNIAI		- 1/ XI I •	Ear 2	07-674-0182	II S	CALE: $1'' = 60'$	12-15-10 E.M		5 OF 1

EXISTING GRADE @ CENTER OF WELL PAD = 4959.21 FINISHED GRADE ELEVATION = 4957.51 CUT SLOPES = 1.5:1FILL SLOPES = 1.5:1**TOTAL WELL PAD AREA = 3.82 ACRES TOTAL DAMAGE AREA = 6.28 ACRES SHRINKAGE FACTOR = 1.10 SWELL FACTOR = 1.00** 

# Kerr-McGee Oil & Gas Onshore, LP

1099 18th Street - Denver, Colorado 80202

# WELL PAD - NBU 922-36G3

**WELL PAD - LOCATION LAYOUT** NBU 922-36G4CS, NBU 922-36F4CS, NBU 922-36F4BS & NBU 922-36G4BS LOCATED IN SECTION 36, T9S, R22E, S.L.B.&M., UINTAH COUNTY, UTAH



2155 North Main Street

Sheridan, WY 82801

Phone 307-674-0609 Fax 307-674-0182

## **WELL PAD QUANTITIES** TOTAL CUT FOR WELL PAD = 19.427 C.Y.

TOTAL FILL FOR WELL PAD = 9,665 C.Y. TOPSOIL @ 6" DEPTH = 1,864 C.Y. EXCESS MATERIAL = 9,762 C.Y.

# **RESERVE PIT QUANTITIES**

**TOTAL CUT FOR RESERVE PIT** +/- 11,020 C.Y. RESERVE PIT CAPACITY (2' OF FREEBOARD) +/- 42,290 BARRELS

# **TIMBERLINE**

ENGINEERING & LAND SURVEYING, INC. 209 NORTH 300 WEST - VERNAL, UTAH 84078

(435) 789-1365

**SCALE:** 

**REVISED:** 


# 8 **EXISTING WELL LOCATION** PROPOSED WELL LOCATION PROPOSED BOTTOM HOLE LOCATION EXISTING CONTOURS (2' INTERVAL) PROPOSED CONTOURS (21 INTERVAL) — PPL — PROPOSED PIPELINE — EPL — EXISTING PIPELINE

60<sup>1</sup> HORIZONTAL E 1" = 60"


21 CONTOURS

1"=60' DATE: 12/3/10 SHEET NO:

b 6 OF 16



# **CROSS SECTION A-A'**



Kerr-McGee Oil & Gas Onshore, LP 1099 18th Street - Denver, Colorado 80202

**WELL PAD - NBU 922-36G3** 

**WELL PAD - CROSS SECTIONS** NBU 922-36G4CS, NBU 922-36F4CS, NBU 922-36F4BS & NBU 922-36G4BS LOCATED IN SECTION 36, T9S, R22E, S.L.B.&M., UINTAH COUNTY, UTAH

# **CROSS SECTION B-B'**



**CONSULTING, LLC** 2155 North Main Street Sheridan, WY 82801 Phone 307-674-0609 Fax 307-674-0182

**HORIZONTAL** 20<sup>1</sup> **VERTICAL** 

TIMBERLINE

**ENGINEERING & LAND SURVEYING, INC.** 209 NORTH 300 WEST - VERNAL, UTAH 84078

Scale: 1"=100' Date: 12/3/10 SHEET NO: 7 OF 16 REVISED:

K:\ANADARKO\2010\_48\_NBU\_FOCUS\_SEC\_36-922\DWGS\NBU 922-36G\NBU\_922-36G\_PAD\_20101103.dvg, 12/7/201




PHOTO VIEW: FROM PIT CORNER D TO LOCATION STAKE





PHOTO VIEW: FROM EXISTING ACCESS ROAD

**CAMERA ANGLE: NORTHERLY** 

#### Kerr-McGee Oil & Gas Onshore, LP 1099 18th Street - Denver, Colorado 80202

## WELL PAD - NBU 922-36G3

**LOCATION PHOTOS** NBU 922-36G4CS, NBU 922-36F4CS, NBU 922-36F4BS & NBU 922-36G4BS LOCATED IN SECTION 36, T9S, R22E, S.L.B.&M., UINTAH COUNTY, UTAH.



#### CONSULTING, LLC 2155 North Main Street Sheridan WY 82801

Phone 307-674-0609 Fax 307-674-0182

T	IM	BE	RI	LIN	٧E	=
	ENC	INE	ERI	NG	&	L


Date Last Revised:


(435) 789-1365


9 OF 16


AND SURVEYING, INC.


١	209 NORTH 300	WEST - VERNAL, UTAH 84	078
п	DATE PHOTOS TAKEN:	PHOTOS TAKEN BY: M.S.B.	SHEET NO:
١	09-02-10	THO TOO IT MEET OF THE MEET	
١	DATE DRAWN:	DRAWN BY: B.M.	Ω
	11-16-10	BRAWN BT. B.M.	. <i>9</i>
ı			














# Kerr-McGee Oil & Gas Onshore, LP WELL PAD – NBU 922-36G3 WELLS – NBU 922-36G4CS, NBU 922-36F4CS, NBU 922-36F4BS & NBU 922-36G4BS Section 36, T9S, R22E, S.L.B.&M.

From the intersection of U.S. Highway 40 and 500 East Street in Vernal, Utah, proceed in an easterly then southerly direction along U.S. Highway 40 approximately 3.3 miles to the junction of State Highway 45. Exit right and proceed in a southerly direction along State Highway 45 approximately 20.2 miles to the junction of the Glen Bench Road (County B Road 3260). Exit right and proceed in a southwesterly direction along the Glen Bench Road approximately 14.4 miles to the intersection of the Fidlar Road (County B Road 3410) which road intersection is approximately 400 feet northeast of the Mountain Fuel Bridge at the White River. Exit left and proceed in a southeasterly direction along the Fidlar Road approximately 4.4 miles to the intersection of the Seven Sisters Road (County B Road 3420). Exit right and proceed in a southerly, then southeasterly direction along the Seven Sisters Road approximately 2.4 miles to a service road to the southwest. Exit right and proceed in a southwesterly, then northerly, then southwesterly direction along the service road approximately 0.7 miles to a second service road approximately 0.1 miles to an access road to the north. Exit right and proceed in a northeasterly direction along the access road approximately 0.1 miles to the proposed well pad.

Total distance from Vernal, Utah to the proposed well location is approximately 45.6 miles in a southerly direction.





Site: NBU 922-36G3 PAD Well: NBU 922-36G4BS


Wellbore: OH

Design: PLAN #1 2-8-11 RHS











# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-36G3 PAD NBU 922-36G4BS

ОН

Plan: PLAN #1 2-8-11 RHS

# **Standard Planning Report**

09 February, 2011





## SDI Planning Report



52,376

EDM5000-RobertS-Local Database:

Company: Kerr McGee Oil and Gas Onshore LP

Uintah County, UT UTM12 Project:

NBU 922-36G3 PAD Site: Well: NBU 922-36G4BS

Wellbore: ОН

Design: PLAN #1 2-8-11 RHS **Local Co-ordinate Reference:** 

**Survey Calculation Method:** 

TVD Reference:

MD Reference:

North Reference:

Well NBU 922-36G4BS GL 4958' & KB 4' @ 4962.00ft (ASSUMED)

GL 4958' & KB 4'

@ 4962.00ft (ASSUMED)

Minimum Curvature

Project Uintah County, UT UTM12

Map System: Universal Transverse Mercator (US Survey Feet)

NAD 1927 - Western US Geo Datum: Zone 12N (114 W to 108 W) Map Zone:

System Datum: Mean Sea Level

65.89

75.02

NBU 922-36G3 PAD, SECTION 36 T9S R22E Site

Northing: 14,527,629.00 usft Site Position: Latitude: 39° 59' 35.250 N From: Lat/Long Easting: 2,092,221.64 usft Longitude: 109° 23' 13.006 W **Position Uncertainty:** 0.00 ft Slot Radius: 13.200 in **Grid Convergence:** 1.04°

Well NBU 922-36G4BS, 2435 FNL 2447 FEL

IGRF2010

**Well Position** +N/-S 29.14 ft 14,527,658.25 usft 39° 59' 35.538 N Northing: Latitude:

+E/-W 6.16 ft Easting: 2,092,227.28 usft Longitude: 109° 23' 12.926 W **Position Uncertainty** 0.00 ft Wellhead Elevation: **Ground Level:** 4.958.00 ft

Wellbore ОН Declination Field Strength Magnetics **Model Name** Sample Date Dip Angle (°) (°) (nT)

11.07

0.00

02/09/2011

0.00

PLAN #1 2-8-11 RHS Design **Audit Notes:** PLAN 0.00 Version: Phase: Tie On Depth: +N/-S Vertical Section: Depth From (TVD) +E/-W Direction (ft) (ft) (ft) (°)

0.00

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,137.50	16.75	75.02	1,125.62	31.43	117.42	2.00	2.00	0.00	75.02	
2,467.71	16.75	75.02	2,399.39	130.54	487.74	0.00	0.00	0.00	0.00	
3,424.85	0.00	0.00	3,342.96	166.46	621.93	1.75	-1.75	0.00	180.00	
8,759.89	0.00	0.00	8,678.00	166.46	621.93	0.00	0.00	0.00	0.00 P	BHL_NBU 922-36G



# **SDI**Planning Report



Database: EDM5000-RobertS-Local

Company: Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12

 Site:
 NBU 922-36G3 PAD

 Well:
 NBU 922-36G4BS

Wellbore: OH

Design: PLAN #1 2-8-11 RHS

Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

**Survey Calculation Method:** 

Well NBU 922-36G4BS

GL 4958' & KB 4'

@ 4962.00ft (ASSUMED)

GL 4958' & KB 4' @ 4962.00ft (ASSUMED)

True

ed Survey									
Magazza			Vertical			Vertical	Doglass	Dila	Tues
Measured Depth	Inclination	Azimuth	Depth	+N/-S	+E/-W	Section	Dogleg Rate	Build Rate	Turn Rate
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
Start Build 2	2.00								
400.00	2.00	75.02	399.98	0.45	1.69	1.75	2.00	2.00	0.00
500.00	4.00	75.02	499.84	1.80	6.74	6.98	2.00	2.00	0.00
600.00	6.00	75.02	599.45	4.06	15.16	15.69	2.00	2.00	0.00
700.00	8.00	75.02	698.70	7.21	26.93	27.88	2.00	2.00	0.00
800.00	10.00	75.02	797.47	11.25	42.04	43.52	2.00	2.00	0.00
900.00	12.00	75.02 75.02	895.62	16.19	60.47	62.60	2.00	2.00	0.00
1,000.00	14.00	75.02	993.06	22.00	82.20	85.10	2.00	2.00	0.00
1,100.00	16.00	75.02	1,089.64	28.69	107.20	110.98	2.00	2.00	0.00
1,137.50	16.75	75.02	1,125.62	31.43	117.42	121.55	2.00	2.00	0.00
Start 1330.2	1 hold at 1137.50	MD							
1,174.45	16.75	75.02	1,161.00	34.18	127.70	132.20	0.00	0.00	0.00
GREEN RIVI	ER								
1,200.00	16.75	75.02	1,185.47	36.08	134.82	139.56	0.00	0.00	0.00
1.300.00	16.75	75.02	1,281.23	43.53	162.66	168.38	0.00	0.00	0.00
1,400.00	16.75	75.02	1,376.98	50.98	190.50	197.20	0.00	0.00	0.00
1,500.00	16.75	75.02	1,472,74	58.44	218.34	226.02	0.00	0.00	0.00
1,600.00	16.75	75.02	1,568.50	65.89	246.18	254.84	0.00	0.00	0.00
1,700.00	16.75	75.02	1,664.26	73.34	274.02	283.66	0.00	0.00	0.00
			,						
1,800.00	16.75	75.02	1,760.01	80.79	301.85	312.48	0.00	0.00	0.00
1,900.00	16.75	75.02	1,855.77	88.24	329.69	341.30	0.00	0.00	0.00
2,000.00	16.75	75.02	1,951.53	95.69	357.53	370.12	0.00	0.00	0.00
2,100.00	16.75	75.02	2,047.28	103.14	385.37	398.94	0.00	0.00	0.00
2,200.00	16.75	75.02	2,143.04	110.59	413.21	427.76	0.00	0.00	0.00
2,300.00	16.75	75.02	2,238.80	118.04	441.05	456.58	0.00	0.00	0.00
2,338.85	16.75	75.02	2,276.00	120.94	451.87	467.77	0.00	0.00	0.00
8 5/8"			,						
2,400.00	16.75	75.02	2,334.56	125.50	468.89	485.40	0.00	0.00	0.00
2,467.71	16.75	75.02	2,399.39	130.54	487.74	504.91	0.00	0.00	0.00
Start Drop -			,						
2,500.00	16.18	75.02	2,430.36	132.91	496.59	514.06	1.75	-1.75	0.00
2,600.00	14.43	75.02	2,526.81	139.73	522.09	540.47	1.75	-1.75	0.00
2,700.00	12.68	75.02	2,624.01	145.79	544.74	563.91	1.75	-1.75	0.00
2,800.00	10.93	75.02	2,721.89	151.09	564.51	584.38	1.75	-1.75	0.00
2,900.00	9.18	75.02	2,820.35	155.60	581.38	601.85	1.75	-1.75	0.00
3,000.00	7.43	75.02	2,919.30	159.34	595.34	616.30	1.75	-1.75	0.00
3,100.00	5.68	75.02	3,018.64	162.29	606.38	627.72	1.75	-1.75	0.00
3,200.00	3.93	75.02	3,118.28	164.46	614.48	636.11	1.75	-1.75	0.00
3,300.00	2.18	75.02	3,218.14	165.84	619.63	641.44	1.75	-1.75	0.00
3,400.00	0.43	75.02	3,318.11	166.43	621.84	643.73	1.75	-1.75	0.00
3,424.85	0.00	0.00	3,342.96	166.46	621.93	643.82	1.75	-1.75	0.00
Start 5335.0	4 hold at 3424.8	5 MD							
3,500.00	0.00	0.00	3,418.11	166.46	621.93	643.82	0.00	0.00	0.00
3,600.00	0.00	0.00	3,518.11	166.46	621.93	643.82	0.00	0.00	0.00
3,700.00	0.00	0.00	3,618.11	166.46	621.93	643.82	0.00	0.00	0.00
3,800.00	0.00	0.00	3,718.11	166.46	621.93	643.82	0.00	0.00	0.00
3,900.00	0.00	0.00	3,818.11	166.46	621.93	643.82	0.00	0.00	0.00



# **SDI**Planning Report



Database: EDM5000-RobertS-Local

Company: Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12

 Site:
 NBU 922-36G3 PAD

 Well:
 NBU 922-36G4BS

Wellbore: OH

Design: PLAN #1 2-8-11 RHS

Local Co-ordinate Reference:

**Survey Calculation Method:** 

TVD Reference:

North Reference:

MD Reference:

GL 4958' & KB 4' @ 4962.00ft (ASSUMED) GL 4958' & KB 4'

Well NBU 922-36G4BS

@ 4962.00ft (ASSUMED)

True

anned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,000.00	0.00	0.00	3,918.11	166.46	621.93	643.82	0.00	0.00	0.00
4,100.00	0.00	0.00	4,018.11	166.46	621.93	643.82	0.00	0.00	0.00
4,200.00	0.00	0.00	4,118.11	166.46	621.93	643.82	0.00	0.00	0.00
4,300.00	0.00	0.00	4,218.11	166.46	621.93	643.82	0.00	0.00	0.00
4,330.89	0.00	0.00	4,249.00	166.46	621.93	643.82	0.00	0.00	0.00
WASATCH			,						
4,400.00	0.00	0.00	4,318.11	166.46	621.93	643.82	0.00	0.00	0.00
4,500.00	0.00	0.00	4,418.11	166.46	621.93	643.82	0.00	0.00	0.00
4,600.00	0.00	0.00	4,518.11	166.46	621.93	643.82	0.00	0.00	0.00
4,700.00	0.00	0.00	4,618.11	166.46	621.93	643.82	0.00	0.00	0.00
,									
4,800.00	0.00	0.00	4,718.11	166.46	621.93	643.82	0.00	0.00	0.00
4,900.00	0.00	0.00	4,818.11	166.46	621.93	643.82	0.00	0.00	0.00
5,000.00	0.00	0.00	4,918.11	166.46	621.93	643.82	0.00	0.00	0.00
5,100.00	0.00	0.00	5,018.11	166.46	621.93	643.82	0.00	0.00	0.00
5,200.00	0.00	0.00	5,118.11	166.46	621.93	643.82	0.00	0.00	0.00
5,300.00	0.00	0.00	5,218.11	166.46	621.93	643.82	0.00	0.00	0.00
5,400.00	0.00	0.00	5,318.11	166.46	621.93	643.82	0.00	0.00	0.00
5,500.00	0.00	0.00	5,418.11	166.46	621.93	643.82	0.00	0.00	0.00
5,600.00	0.00	0.00	5,518.11	166.46	621.93	643.82	0.00	0.00	0.00
5,700.00	0.00	0.00	5,618.11	166.46	621.93	643.82	0.00	0.00	0.00
5,800.00	0.00	0.00	5,718.11	166.46	621.93	643.82	0.00	0.00	0.00
5,900.00	0.00	0.00	5,818.11	166.46	621.93	643.82	0.00	0.00	0.00
6,000.00	0.00	0.00	5,918.11	166.46	621.93	643.82	0.00	0.00	0.00
6,100.00	0.00	0.00	6,018.11	166.46	621.93	643.82	0.00	0.00	0.00
6,200.00	0.00	0.00	6,118.11	166.46	621.93	643.82	0.00	0.00	0.00
6,300.00	0.00	0.00	6,218.11	166.46	621.93	643.82	0.00	0.00	0.00
6,400.00	0.00	0.00	6,318.11	166.46	621.93	643.82	0.00	0.00	0.00
6,500.00	0.00	0.00	6,418.11	166.46	621.93	643.82	0.00	0.00	0.00
6,543.89	0.00	0.00	6,462.00	166.46	621.93	643.82	0.00	0.00	0.00
MESAVERD		2.22	0.540.44	100.10	204.00	0.40.00	0.00	2.22	0.00
6,600.00	0.00	0.00	6,518.11	166.46	621.93	643.82	0.00	0.00	0.00
6,700.00	0.00	0.00	6,618.11	166.46	621.93	643.82	0.00	0.00	0.00
6,800.00	0.00	0.00	6,718.11	166.46	621.93	643.82	0.00	0.00	0.00
6,900.00	0.00	0.00	6,818.11	166.46	621.93	643.82	0.00	0.00	0.00
7,000.00	0.00	0.00	6,918.11	166.46	621.93	643.82	0.00	0.00	0.00
7,100.00	0.00	0.00	7,018.11	166.46	621.93	643.82	0.00	0.00	0.00
7,200.00	0.00	0.00	7,118.11	166.46	621.93	643.82	0.00	0.00	0.00
7,300.00	0.00	0.00	7,218.11	166.46	621.93	643.82	0.00	0.00	0.00
7,400.00	0.00	0.00	7,318.11	166.46	621.93	643.82	0.00	0.00	0.00
7,500.00	0.00	0.00	7,418.11	166.46	621.93	643.82	0.00	0.00	0.00
7,600.00	0.00	0.00	7,518.11	166.46	621.93	643.82	0.00	0.00	0.00
7,700.00	0.00	0.00	7,618.11	166.46	621.93	643.82	0.00	0.00	0.00
7,800.00	0.00	0.00	7,718.11	166.46	621.93	643.82	0.00	0.00	0.00
7,900.00	0.00	0.00	7,818.11	166.46	621.93	643.82	0.00	0.00	0.00
8,000.00	0.00	0.00	7,918.11	166.46	621.93	643.82	0.00	0.00	0.00
8,100.00	0.00	0.00	8,018.11	166.46	621.93	643.82	0.00	0.00	0.00
8,200.00	0.00	0.00	8,118.11	166.46	621.93	643.82	0.00	0.00	0.00
8,300.00	0.00	0.00	8,218.11	166.46	621.93	643.82	0.00	0.00	0.00
8,400.00	0.00	0.00	8,318.11	166.46	621.93	643.82	0.00	0.00	0.00
8,500.00	0.00	0.00	8,418.11	166.46	621.93	643.82	0.00	0.00	0.00
8,600.00	0.00	0.00	8,518.11	166.46	621.93	643.82	0.00	0.00	0.00
8,700.00	0.00	0.00	8,618.11	166.46	621.93	643.82	0.00	0.00	0.00



## SDI Planning Report



Database: Company: EDM5000-RobertS-Local

Kerr McGee Oil and Gas Onshore LP

MD Reference:

TVD Reference:

North Reference:

Local Co-ordinate Reference:

**Survey Calculation Method:** 

Well NBU 922-36G4BS

GL 4958' & KB 4'

@ 4962.00ft (ASSUMED)

GL 4958' & KB 4' @ 4962.00ft (ASSUMED)

True Minimum Curvature

Project:

Uintah County, UT UTM12

Site: Well: NBU 922-36G3 PAD

Wellbore:

NBU 922-36G4BS

Design: PLAN #1 2-8-11 RHS

**Planned Survey** 

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
8,759.89	0.00	0.00	8,678.00	166.46	621.93	643.82	0.00	0.00	0.00

PBHL\_NBU 922-36G4BS

**Design Targets** 

**Target Name** - hit/miss target Dip Angle

- Shape

(°) PBHL\_NBU 922-36G4B

0.00

Dip Dir.

(°) (ft) 0.00 8,678.00

TVD

+N/-S (ft) 166.46

Name

+E/-W (ft) 621.93

(usft) 14,527,835.93

Northing

(usft) 2,092,846.10

Lithology

Easting

Latitude 39° 59' 37.183 N

Dip

Direction

(°)

Dip

Longitude 109° 23' 4.934 W

- plan hits target center - Circle (radius 25.00)

**Casing Points** 

Casing Vertical Hole Measured Depth Depth Diameter Diameter (ft) (ft) (in) (in) Name 2,338.85 2,276.00 8 5/8" 8.625 11.000

**Formations** 

Measured Depth Depth (ft) (ft) 1,174.45 1,161.00 GREEN RIVER 4,330.89 4,249.00 WASATCH

6,462.00 MESAVERDE

Vertical

6,543.89

Plan Annotati	ons				
	Measured	Vertical	Local Coor	dinates	
	Depth	Depth	+N/-S	+E/-W	
	(ft)	(ft)	(ft)	(ft)	Comment
	300.00	300.00	0.00	0.00	Start Build 2.00
	1,137.50	1,125.62	31.43	117.42	Start 1330.21 hold at 1137.50 MD
	2,467.71	2,399.39	130.54	487.74	Start Drop -1.75
	3,424.85	3,342.96	166.46	621.93	Start 5335.04 hold at 3424.85 MD
	8,759.89	8,678.00	166.46	621.93	TD at 8759.89



# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-36G3 PAD NBU 922-36G4BS

OH

Plan: PLAN #1 2-8-11 RHS

# **Standard Planning Report - Geographic**

09 February, 2011





# SDI Planning Report - Geographic



EDM5000-RobertS-Local Database:

Company: Kerr McGee Oil and Gas Onshore LP

Uintah County, UT UTM12

NBU 922-36G3 PAD Site:

Well: NBU 922-36G4BS

Wellbore: ОН

Project:

Design: PLAN #1 2-8-11 RHS **Local Co-ordinate Reference:** 

**Survey Calculation Method:** 

**TVD Reference:** 

MD Reference:

North Reference:

Well NBU 922-36G4BS GL 4958' & KB 4'

@ 4962.00ft (ASSUMED)

GL 4958' & KB 4' @ 4962.00ft (ASSUMED)

Minimum Curvature

Project Uintah County, UT UTM12

Universal Transverse Mercator (US Survey Feet) Map System:

NAD 1927 - Western US Geo Datum: Map Zone: Zone 12N (114 W to 108 W)

Mean Sea Level System Datum:

Site NBU 922-36G3 PAD, SECTION 36 T9S R22E

14,527,629.00 usft Site Position: Northing: Latitude: 39° 59' 35.250 N 2,092,221.64 usft 109° 23' 13.006 W Lat/Long Easting: From: Longitude: 0.00 ft Slot Radius: 13.200 in 1.04 9 **Position Uncertainty: Grid Convergence:** 

NBU 922-36G4BS, 2435 FNL 2447 FEL Well **Well Position** +N/-S 0.00 ft Northing: 14,527,658.25 usft Latitude: 39° 59' 35.538 N +E/-W 0.00 ft 2,092,227.28 usft Longitude: 109° 23' 12.926 W Easting: 0.00 ft 4,958.00 ft **Position Uncertainty** Wellhead Elevation: **Ground Level:** 

Wellbore ОН Magnetics **Model Name** Sample Date Declination Dip Angle Field Strength (nT) (°) 02/09/2011 65.89 IGRF2010 11.07 52,376

PLAN #1 2-8-11 RHS Design **Audit Notes:** PLAN 0.00 Version: Phase: Tie On Depth: +N/-S Vertical Section: Depth From (TVD) +E/-W Direction (ft) (ft) (ft) (°) 0.00 0.00 0.00 75.02

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,137.50	16.75	75.02	1,125.62	31.43	117.42	2.00	2.00	0.00	75.02	
2,467.71	16.75	75.02	2,399.39	130.54	487.74	0.00	0.00	0.00	0.00	
3,424.85	0.00	0.00	3,342.96	166.46	621.93	1.75	-1.75	0.00	180.00	
8,759.89	0.00	0.00	8,678.00	166.46	621.93	0.00	0.00	0.00	0.00 P	BHL_NBU 922-36G



# **SDI**Planning Report - Geographic



Database: EDM5000-RobertS-Local

Company: Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12

 Site:
 NBU 922-36G3 PAD

 Well:
 NBU 922-36G4BS

Wellbore: OH

Design: PLAN #1 2-8-11 RHS

Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

**Survey Calculation Method:** 

Well NBU 922-36G4BS

GL 4958' & KB 4'

@ 4962.00ft (ASSUMED) GL 4958' & KB 4'

@ 4962.00ft (ASSUMED)

True

ned Survey									
Measured Depth (ft)	Inclination	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitudo
						, ,			Longitude
0.00	0.00	0.00	0.00	0.00	0.00	14,527,658.25	2,092,227.28	39° 59' 35.538 N	109° 23' 12.926 \
100.00	0.00	0.00	100.00	0.00	0.00	14,527,658.25	2,092,227.28	39° 59' 35.538 N	109° 23' 12.926 \
200.00	0.00	0.00	200.00	0.00	0.00	14,527,658.25	2,092,227.28	39° 59' 35.538 N	109° 23' 12.926 \
300.00	0.00	0.00	300.00	0.00	0.00	14,527,658.25	2,092,227.28	39° 59' 35.538 N	109° 23' 12.926 \
Start Bu									
400.00	2.00	75.02	399.98	0.45	1.69	14,527,658.73	2,092,228.95	39° 59' 35.542 N	109° 23' 12.905
500.00	4.00	75.02	499.84	1.80	6.74	14,527,660.17	2,092,233.98	39° 59' 35.556 N	109° 23' 12.840
600.00	6.00	75.02	599.45	4.06	15.16	14,527,662.58	2,092,242.36	39° 59' 35.578 N	109° 23' 12.732
700.00	8.00	75.02	698.70	7.21	26.93	14,527,665.94	2,092,254.07	39° 59' 35.609 N	109° 23' 12.580
800.00	10.00	75.02	797.47	11.25	42.04	14,527,670.26	2,092,269.11	39° 59' 35.649 N	109° 23' 12.386
900.00	12.00	75.02	895.62	16.19	60.47	14,527,675.52	2,092,287.45	39° 59' 35.698 N	109° 23' 12.149
1,000.00	14.00	75.02	993.06	22.00	82.20	14,527,681.73	2,092,309.07	39° 59' 35.755 N	109° 23' 11.870
1,100.00	16.00	75.02	1,089.64	28.69	107.20	14,527,688.87	2,092,333.94	39° 59' 35.822 N	109° 23' 11.549
1,137.50	16.75	75.02	1,125.62	31.43	117.42	14,527,691.79	2,092,344.11	39° 59' 35.849 N	109° 23' 11.418
	30.21 hold at 1								
1,174.45	16.75	75.02	1,161.00	34.18	127.70	14,527,694.73	2,092,354.34	39° 59' 35.876 N	109° 23' 11.285
GREEN									
1,200.00	16.75	75.02	1,185.47	36.08	134.82	14,527,696.76	2,092,361.42	39° 59' 35.895 N	109° 23' 11.194
1,300.00	16.75	75.02	1,281.23	43.53	162.66	14,527,704.72	2,092,389.12	39° 59' 35.968 N	109° 23' 10.836
1,400.00	16.75	75.02	1,376.98	50.98	190.50	14,527,712.67	2,092,416.82	39° 59' 36.042 N	109° 23' 10.478
1,500.00	16.75	75.02	1,472.74	58.44	218.34	14,527,720.62	2,092,444.52	39° 59' 36.116 N	109° 23' 10.121
1,600.00	16.75	75.02	1,568.50	65.89	246.18	14,527,728.58	2,092,472.22	39° 59' 36.189 N	109° 23' 9.763
1,700.00	16.75	75.02	1,664.26	73.34	274.02	14,527,736.53	2,092,499.92	39° 59' 36.263 N	109° 23' 9.405
1,800.00	16.75	75.02	1,760.01	80.79	301.85	14,527,744.49	2,092,527.62	39° 59' 36.337 N	109° 23' 9.048
1,900.00	16.75	75.02	1,855.77	88.24	329.69	14,527,752.44	2,092,555.32	39° 59' 36.410 N	109° 23' 8.690
2,000.00	16.75	75.02	1,951.53	95.69	357.53	14,527,760.39	2,092,583.02	39° 59' 36.484 N	109° 23' 8.332
2,100.00	16.75	75.02	2,047.28	103.14	385.37	14,527,768.35	2,092,610.72	39° 59' 36.557 N	109° 23' 7.974
2,200.00	16.75	75.02 75.02	2,143.04	110.59	413.21	14,527,776.30	2,092,638.42	39° 59' 36.631 N	109° 23' 7.617
2,300.00	16.75	75.02	2,238.80	118.04	441.05	14,527,784.25	2,092,666.12	39° 59' 36.705 N	109° 23' 7.259
2,338.85	16.75	75.02	2,276.00	120.94	451.87	14,527,787.34	2,092,676.88	39° 59' 36.733 N	109° 23' 7.120
<b>8 5/8"</b> 2,400.00	16.75	75.02	2,334.56	125.50	468.89	14,527,792.21	2,092,693.82	39° 59' 36.778 N	109° 23' 6.901
	16.75	75.02 75.02		130.54	487.74				
2,467.71		75.02	2,399.39	130.54	487.74	14,527,797.59	2,092,712.58	39° 59' 36.828 N	109° 23' 6.659
Start Dro	•	75.02	2,430.36	132.91	496.59	14,527,800.12	2 002 724 22	39° 59' 36.852 N	100° 22' 6 E4E
2,500.00	16.18						2,092,721.38		109° 23' 6.545
2,600.00	14.43	75.02	2,526.81	139.73	522.09	14,527,807.41	2,092,746.75	39° 59' 36.919 N	109° 23' 6.217
2,700.00	12.68	75.02	2,624.01	145.79	544.74	14,527,813.88	2,092,769.29	39° 59' 36.979 N	109° 23' 5.926
2,800.00	10.93	75.02	2,721.89	151.09	564.51	14,527,819.52	2,092,788.96	39° 59' 37.031 N	109° 23' 5.672
2,900.00	9.18	75.02	2,820.35	155.60	581.38	14,527,824.35	2,092,805.75	39° 59' 37.076 N	109° 23' 5.455
3,000.00	7.43	75.02	2,919.30	159.34	595.34	14,527,828.33	2,092,819.64	39° 59' 37.113 N	109° 23' 5.276
3,100.00	5.68	75.02	3,018.64	162.29	606.38	14,527,831.49	2,092,830.62	39° 59' 37.142 N	109° 23' 5.134
3,200.00	3.93	75.02	3,118.28	164.46	614.48	14,527,833.80	2,092,838.68	39° 59' 37.163 N	109° 23' 5.030
3,300.00	2.18	75.02	3,218.14	165.84	619.63	14,527,835.27	2,092,843.81	39° 59' 37.177 N	109° 23' 4.964
3,400.00	0.43	75.02	3,318.11	166.43	621.84	14,527,835.90	2,092,846.01	39° 59' 37.183 N	109° 23' 4.936
3,424.85	0.00	0.00	3,342.96	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934
	35.04 hold at 3	424.85 MD							
3,500.00	0.00	0.00	3,418.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934
3,600.00	0.00	0.00	3,518.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934
3,700.00	0.00	0.00	3,618.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934
3,800.00	0.00	0.00	3,718.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934
3,900.00	0.00	0.00	3,818.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934
4,000.00	0.00	0.00	3,918.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934



# SDI Planning Report - Geographic



EDM5000-RobertS-Local Database:

Company: Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12

Site: NBU 922-36G3 PAD Well: NBU 922-36G4BS

Wellbore:

Design: PLAN #1 2-8-11 RHS Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

**Survey Calculation Method:** 

Well NBU 922-36G4BS

GL 4958' & KB 4'

@ 4962.00ft (ASSUMED) GL 4958' & KB 4'

@ 4962.00ft (ASSUMED)

True

Planned Su	rvey								
	•								
Measur			Vertical			Мар	Мар		
Depth		Azimuth	Depth	+N/-S	+E/-W	Northing	Easting		
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(usft)	(usft)	Latitude	Longitude
4,100	0.00	0.00	4,018.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
4,200	0.00	0.00	4,118.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
4,300	0.00	0.00	4,218.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
4,330	0.00	0.00	4,249.00	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
WAS	SATCH								
4,400			4,318.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
4,500			4,418.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
4,600			4,518.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
4,700			4,618.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
4,800			4,718.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
4,900			4,818.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
5,000			4,918.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
5,100 5,200			5,018.11 5,118.11	166.46 166.46	621.93 621.93	14,527,835.93 14,527,835.93	2,092,846.10 2,092,846.10	39° 59' 37.183 N 39° 59' 37.183 N	109° 23' 4.934 W 109° 23' 4.934 W
5,300			5,118.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
5,400			5,318.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
5,500			5,418.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
5,600			5,518.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
5,700			5,618.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
5,800			5,718.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
5,900	0.00	0.00	5,818.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
6,000	0.00	0.00	5,918.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
6,100	0.00	0.00	6,018.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
6,200	0.00	0.00	6,118.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
6,300	0.00	0.00	6,218.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
6,400			6,318.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
6,500			6,418.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
6,543	3.89 0.00	0.00	6,462.00	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
	AVERDE								
6,600			6,518.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
6,700			6,618.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
6,800			6,718.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
6,900			6,818.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
7,000 7,100			6,918.11 7,018.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N 39° 59' 37.183 N	109° 23' 4.934 W
7,100			7,018.11	166.46 166.46	621.93 621.93	14,527,835.93 14,527,835.93	2,092,846.10 2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W 109° 23' 4.934 W
7,200			7,118.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
7,400			7,318.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
7,500			7,418.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
7,600			7,518.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
7,700			7,618.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
7,800			7,718.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
7,900			7,818.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
8,000		0.00	7,918.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
8,100	0.00	0.00	8,018.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
8,200	0.00	0.00	8,118.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
8,300			8,218.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
8,400			8,318.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
8,500			8,418.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
8,600			8,518.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W
8,700	0.00 0.00	0.00	8,618.11	166.46	621.93	14,527,835.93	2,092,846.10	39° 59' 37.183 N	109° 23' 4.934 W



# **SDI**Planning Report - Geographic



Database: EDM Company: Kerr

EDM5000-RobertS-Local

Kerr McGee Oil and Gas Onshore LP

Project:

Uintah County, UT UTM12

 Site:
 NBU 922-36G3 PAD

 Well:
 NBU 922-36G4BS

Wellbore: OF

Design: PLAN #1 2-8-11 RHS

Local Co-ordinate Reference:

**Survey Calculation Method:** 

TVD Reference:

MD Reference:

North Reference:

Well NBU 922-36G4BS GL 4958' & KB 4' @ 4962.00ft (ASSUMED)

GL 4958' & KB 4'

@ 4962.00ft (ASSUMED)

True

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
8,759.89	0.00	0.00	8,678.00	166.46	621.93	14,527,835.93	2,092,846.10	39° 59′ 37.183 N	109° 23' 4.934 W

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL_NBU 922-36G4B - plan hits target cent - Circle (radius 25.00		0.00	8,678.00	166.46	621.93	14,527,835.93	2,092,846.10	39° 59′ 37.183 N	109° 23' 4.934 W

Casing Points					
	Measured	Vertical		Casing	Hole
	Depth	Depth		Diameter	Diameter
	(ft)	(ft)	Name	(in)	(in)
	2,338.85	2,276.00 8 5/8"		8.625	11.000

Formations							
	Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)	
	1,174.45	1,161.00	GREEN RIVER				
	4,330.89	4,249.00	WASATCH				
	6,543.89	6,462.00	MESAVERDE				

an Annotations					
Measu	red	Vertical	Local Coord	dinates	
Depti	h	Depth	+N/-S	+E/-W	
(ft)		(ft)	(ft)	(ft)	Comment
30	0.00	300.00	0.00	0.00	Start Build 2.00
1,13	7.50	1,125.62	31.43	117.42	Start 1330.21 hold at 1137.50 MD
2,46	7.71	2,399.39	130.54	487.74	Start Drop -1.75
3,42	4.85	3,342.96	166.46	621.93	Start 5335.04 hold at 3424.85 MD
8,75	9.89	8,678.00	166.46	621.93	TD at 8759.89

#### **NBU 922-36F4BS**

Surface: 2414' FNL 2443' FEL (SW/4NE/4) BHL: 2070' FNL 2149' FWL (SE/4NW/4)

#### **NBU 922-36F4CS**

Surface: 2424' FNL 2445' FEL (SW/4NE/4) BHL: 2401' FNL 2149' FWL (SE/4NW/4)

#### **NBU 922-36G4BS**

Surface: 2405' FNL 2441' FEL (SW/4NE/4) BHL: 2235' FNL 1818' FEL (SW/4NE/4)

#### **NBU 922-36G4CS**

Surface: 2434' FNL 2447' FEL (SW/4NE/4) BHL: 2566' FNL 1818' FEL (SW/4NE/4)

> Pad: NBU 922-36G3 Pad Section 36 T09S R22E Mineral Lease: ML-22650

Uintah County, Utah Operator: Kerr-McGee Oil & Gas Onshore LP

#### MULTI-POINT SURFACE USE PLAN of OPERATIONS (SUPO)

This SUPO contains surface operating procedures for Kerr-McGee Oil & Gas Onshore LP (KMG), a wholly owned subsidiary of Anadarko Petroleum Corporation (APC) pertaining to actions that involve the State of Utah School and Institutional Trust Lands Administration (SITLA) in the development of minerals leased to KMG (including, but not limited to, APDs/SULAs/ROEs/ROWs and/or easements).

See associated Utah Division of Oil, Gas, and Mining (UDOGM) Form 3(s), plats, maps, and other attachments for site-specific information on projects represented herein.

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, these wells will be directionally drilled. Refer to Topo Map A for directions to the location and Topo Maps A and B for location of access roads within a 2-mile radius.

#### A. <u>Existing Roads</u>:

Existing roads consist of county roads and improved/unimproved lease roads. KMG will maintain existing roads in a condition that is the same as or better than before operations began and in a safe and usable condition. Maintenance of existing roads will continue until final abandonment and reclamation of well pads and/or other facilities. The road maintenance may include, but is not limited to, blading, ditching, culvert installation/cleanout, surfacing, and dust control.

Typically, roads, gathering lines and electrical distribution lines will occupy common disturbance corridors and roadways will be used as working space. All disturbances located in the same corridor will overlap each

NBU 922-36F4BS / 36F4CS/ 36G4BS/ 36G4CS

Surface Use Plan of Operations Page 2

other to the maximum extent possible; in no case will the maximum disturbance width of the access road and utility corridors exceed 50', unless otherwise approved.

#### **B.** Planned Access Roads:

No new access road is proposed. (see Topo Map B). Applicable Uintah County encroachment and/or pipeline crossing permits will be obtained prior to construction/development. No other pipelines will be crossed at this location.

If there are roads that are new or to be reconstructed, they will be located, designed, and maintained to meet the standards of SITLA and other commonly accepted Best Management Practices (BMPs). If a new road/corridor were to cross a water of the United States, KMG will adhere to the requirements of applicable Nationwide or Individual Permits of the Department of Army Corps of Engineers.

During the onsite, turnouts, major cut and fills, culverts, bridges, gates, cattle guards, low water crossings, or modifications needed to existing infrastructure/facilities were determined, as applicable, are typically shown on attached Exhibits and Topo maps.

## C. <u>Location of Existing and Proposed Facilities</u>:

This pad will expand the existing pad for the NBU 922-36G. The NBU 922-36G well location is a vertical producing well according to Utah Division of Oil, Gas and Mining (UDOGM) records as of April 15, 2011.

Production facilities (see Well Pad Design Summary and Facilities Diagram):

Production facilities will be installed on the disturbed portion of the well pad and may include bermed components (typically excluding dehy's and/or separators) that contain fluids (i.e. production tanks, produced liquids tanks). The berms will be constructed of compacted subsoil or corrugated metal, impervious, designed to hold 110% of the capacity of the largest tank, and be independent of the back cut. All permanent (on-site six months or longer) above ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earth-tone color chosen at the onsite in coordination with SITLA.

Production tanks will be constructed, maintained, and operated to prevent unauthorized surface or subsurface discharges of liquids and to prevent livestock or wildlife entry. The tanks are not to be used for disposal of liquids from additional sources without prior approval of UDOGM.

## **Gathering facilities:**

#### NBU 922-36F4BS / 36F4CS/ 36G4BS/ 36G4CS

## Surface Use Plan of Operations Page 3

The following pipeline transmission facilities will apply if the well is productive (see Topo D):

The total gas gathering (steel line pipe with fusion bond epoxy coating) pipeline distances from the meter to the tie in point is  $\pm 1,720$ ' and the individual segments are broken up as follows:

- ±675' (0.1 miles) –New 6" buried gas pipeline from the meter to the edge of the pad. Please refer to Topo D2.
- ±485' (0.09 miles) –New 6" buried gas pipeline from the edge of pad to the proposed 16" tie-in at the 36I intersection. Please refer to Topo D.
- $\pm 560$ ' (0.1 miles) –New 16" buried gas pipeline from the proposed 16" tie-in at the 36I intersection to the tie-in at the 36O intersection. Please refer to Topo D.

The total liquid gathering pipeline distance from the separator to the tie in point is  $\pm 1,720$ ' and the individual segments are broken up as follows:

- ±675' (0.1 miles) –New 6" buried liquid pipeline from the separator to the edge of the pad. Please refer to Topo D2.
- ±485' (0.09 miles) –New 6" buried liquid pipeline from the edge of pad to the proposed 6" tie-in at the 36I intersection. Please refer to Topo D.
- $\pm 560$ ' (0.1 miles) –New 6" buried liquid pipeline from the proposed 6" tie-in at the 36I intersection to the tie-in at the 36O intersection. Please refer to Topo D.

The liquid gathering lines will be made of polyethylene or a composite polyethylene/steel or polyethylene/fiberglass that is not subject to internal or external pipe corrosion. The content of the produced fluids to be transferred by the liquid gathering system will be approximately 92% produced water and 8% condensate. Trunk line valve connections for the water gathering system will be below ground but accessible from the surface in order to prevent freezing during winter time.

The proposed pipelines will be buried and will include gas gathering and liquid gathering pipelines in the same trench. Where the pipeline is adjacent to the road or well pad, the road and/or well pad will be utilized for construction activities and staging. KMG requests a permanent 30' right-of-way adjacent to the road for life-of-project for maintenance, repairs, and/or upgrades, no additional right-of-way will be needed beyond the 30'. Where the pipeline is not adjacent to the road or well pad, KMG requests a temporary 45' construction right-of-way and 30' permanent right-of-way.

The proposed trench width for the pipeline would range from 18-48 inches and will be excavated to a depth of 48 to 60 inches of normal soil cover or 24 inches of cover in consolidated rock. During construction blasting may occur along the proposed right-of-way where trenching equipment cannot cut into the bedrock. Large debris and rocks removed from the earth during trenching and blasting that could not be returned to the trench would be distributed evenly and naturally in the project area. The proposed pipelines will be pressure tested pneumatically (depending on size) or with fluids (either fresh or produced). If fluids are used, there will be no discharge to the surface.

NBU 922-36F4BS / 36F4CS/ 36G4BS/ 36G4CS

Surface Use Plan of Operations Page 4

Pipeline signs will be installed along the right-of-way to indicate the pipeline proximity and ownership, as well as to provide emergency contact phone numbers. Above ground valves, T's, and/or cathodic protection will be installed at various locations for connection, corrosion prevention and/or for safety purposes.

#### D. <u>Location and Type of Water Supply:</u>

Water for drilling purposes will be obtained from one of the following sources:

- Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32 T4S R3E, Water User Claim number 43-8496, application number 53617.
- Price Water Pumping Inc. Green River and White River, various sources, Water Right Number 49-1659, application number: a35745.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

#### **E.** Source of Construction Materials:

Construction operations will typically be completed with native materials found on location. If needed, construction materials that must be imported to the site (mineral material aggregate, soils or materials suitable for fill/surfacing) will be obtained from a nearby permitted source and described in subsequent Sundry requests. No construction materials will be removed from State lands without prior approval from SITLA.

#### F. Methods of Handling Waste Materials:

Should the well be productive, produced water will be contained in a water tank and will be transported by pipeline and/or truck to an approved disposal sites facilities and/or Salt Water Disposal (SWD) injection well. Currently, those facilities are:

RNI in Sec. 5 T9S R22E

Ace Oilfield in Sec. 2 T6S R20E MC&MC in Sec. 12 T6S R19E Pipeline Facility in Sec. 36 T9S R20E

Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E

Bonanza Evaporation Pond in Sec. 2 T10S R23E

Ouray #1 SWD in Sec. 1 T9S R21E NBU 159 SWD in Sec. 35 T9S R21E CIGE 112D SWD in Sec. 19 T9S R21E CIGE 114 SWD in Sec. 34 T9S R21E NBU 921-34K SWD in Sec. 34 T9S R21E

NBU 922-36F4BS / 36F4CS/ 36G4BS/ 36G4CS

Surface Use Plan of Operations Page 5

NBU 921-33F SWD in Sec. 33 T9S R21E NBU 921-34L SWD in Sec. 34 T9S R21E

Drill cuttings and/or fluids will be contained in the reserve/frac pit. Cuttings will be buried in pit(s) upon closure. Unless otherwise approved, no oil or other oil-based drilling additives, chromium/metals-based, or saline muds will be used during drilling. Only fresh water (as specified above), biodegradable polymer soap, bentonite clay, and/or non-toxic additives will be used in the mud system.

Pits will be constructed to minimize the accumulation of surface runoff. Should fluid hydrocarbons be encountered during drilling, completions or well testing, product will either be contained in test tanks on the well site or evacuated by vacuum trucks and transported to an approved disposal/sales facility. Should petroleum hydrocarbons unexpectedly be released into a pit, they will be removed as soon as practical but in no case will they remain longer than 72 hours unless an alternate is approved by SITLA. Should timely removal prove infeasible, the pit will be netted with mesh no larger than 1 inch until such time as hydrocarbons can be removed. Hydrocarbon removal will also take place prior to the closure of the pit, unless authorization is provided for disposal via alternative pit closure methods (e.g. solidification).

The reserve and/or fracture stimulation pit will be lined with a synthetic material 20-mil or thicker, The liner will be installed over smooth fill subgrade that is free of pockets, loose rocks, or other materials (i.e. sand, sifted dirt, bentonite, straw, etc.) that could damage the liner. Any additional pits necessary for subsequent operations, such as temporary flare or workover pits, will be contained within the originally approved well pad and disturbance boundaries. Such temporary pits will be backfilled and reclaimed within 180 days of completion of work at a well location.

For the protection of livestock and wildlife, all open pits and cellars will be fenced/covered to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

Pits containing drilling cuttings, mud, and/or completions fluids will be allowed to dry. Any free fluids remaining after six (6) months from reaching total depth, date of completion, and/or determination of inactivity will be removed (as weather conditions allow) to an approved site and the pit reclaimed. Additional drying methods may include fly-ash solidification or sprinkler evaporation. Installation and operation of any sprinklers, pumps, and equipment will ensure that water spray or mist does not drift. Reserve pit liners will be cut off or folded as near to the mud surface as possible and as safety considerations allow and buried on location.

No garbage or non-exempt substances as defined by Resource Conservation and Recovery Act (RCRA) subtitle C will be placed in the reserve pit. All refuse generated during construction, drilling, completion, and well testing activities will be contained in an enclosed receptacle, removed from the drill locations promptly,

NBU 922-36F4BS / 36F4CS/ 36G4BS/ 36G4CS

Surface Use Plan of Operations Page 6

and transported to an approved disposal facility.

Portable, self-contained chemical toilets and/or sewage processing facilities will be provided for human waste disposal. Upon completion of operations, or as required, the toilet holding tanks will be pumped and the contents disposed of in an approved sewage disposal facility. All applicable regulations pertaining to disposal of human and solid waste will be observed.

Any undesirable event, including accidental release of fluids, or release in excess of reportable quantities, will be managed according to the notification requirements of UDOGMs "Reporting Oil and Gas Undesirable Events" rule. Where State wells are participatory to a Federal agreement, according to NTL-3A, the appropriate Federal agencies will be notified.

## **Materials Management**

Hazardous materials above reportable quantities will not be produced by drilling or completing proposed wells or constructing the pipelines/facilities. The term "hazardous materials" as used here means: (1) any substance, pollutant, or containment listed as hazardous under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980, as amended 42 U.S.C. 9601 et seq., and the regulations issued under CERCLA; and (2) any hazardous waste as defined in RCRA of 1976, as amended. In addition, no extremely hazardous substance, as defined in 40 CFR 355, in threshold planning quantities, would be used, produced, stored, transported, or disposed of while producing any well.

Chemicals subject to reporting under Title III of the Superfund Amendments and Reauthorization Act (SARA) in quantities of 10,000 pounds or more may be produced and/or stored at production facilities and may be kept in limited quantities on drilling sites and well locations for short periods of time during drilling or completion activities.

## G. <u>Ancillary Facilities</u>:

None are anticipated.

## H. Well Site Layout (see Well Pad Design Summary):

The location, orientation and aerial extent of each drill pad, reserve/completion/flare pit, access road ingress/egress points, drilling rig, dikes/ditches, existing wells/infrastructure, proposed cuts and fills, and topsoil and spoil material stockpile locations are depicted on the exhibits for each project where applicable. Site-specific conditions may require slight deviation in actual equipment and facility layout; however, the area of disturbance, as described in the survey, will not be exceeded.

Coordinates are provided in the National Spatial Reference System, North American Datum, 1927 (NAD27) or latest edition. Distances are depicted on each plat to the nearest two adjacent section lines.

## I. Plans for Reclamation of the Surface:

NBU 922-36F4BS / 36F4CS/ 36G4BS/ 36G4CS

Surface Use Plan of Operations Page 7

Surface reclamation will be undertaken in two phases: interim and final. Interim reclamation is conducted following well completion and extends through the period of production. This reclamation is for the area of the well pad that is not required for production activities. Final reclamation is conducted following well plugging/conversion and/or facility abandonment processes.

Reclamation activities in both phases may include but are not limited to: re-contouring or re-configuration of topographic surfaces, restoration of drainage systems, segregation of spoils materials, minimizing surface disturbance, re-evaluating backfill requirements, pit closure, topsoil redistribution, soil treatments, seeding and weed control.

## **Interim Reclamation**

Interim reclamation includes pit closure, re-contouring (where possible), soil bed preparation, topsoil placement, seeding, and/or weed control.

Interim re-contouring involves bringing all construction material from cuts and fills back onto the well pad and site and reestablishing the natural contours where desirable and practical. Fill and stockpiled spoils no longer necessary to the operation will be spread on the cut slopes and covered with stockpiled topsoil. All stockpiled top soils will be used for interim reclamation where practical to maintain soil viability. Where possible, the land surface will be left "rough" after re-contouring to ensure that the maximum surface area will be available to support the reestablishment of vegetative cover.

A reserve pit, upon being allowed to dry, will be backfilled and compacted with cover materials that are void of any topsoil, vegetation, large stones, rocks or foreign objects. Soils that are moisture laden, saturated, or partially/completely frozen will not be used for backfill or cover. The pit area will be mounded to allow for settling and to promote positive surface drainage away from the pit.

#### **Final Reclamation**

Final reclamation will be performed for newly drilled unproductive wells and/or at the end of the life of a productive well. As soon as practical after the conclusion of drilling and testing operations, unproductive drill holes will be plugged and abandoned (P&A). Site and road reclamation will commence following plugging. In no case will reclamation at non-producing locations be initiated later than six (6) months from the date a well is plugged. A joint inspection of the disturbed area to be reclaimed may be requested by KMG. The primary purpose of this inspection will be to review the existing conditions, or agree upon a revised final reclamation and abandonment plan. A Notice of Intent to Abandon will be filed for final recommendations regarding surface reclamation.

After plugging, all wellhead equipment that is no longer needed will be removed, and the well site will be reclaimed. Final contouring will blend with and follow as closely as practical the natural terrain and contours of the original site and surrounding areas. After re-contouring, final grading will be conducted over the entire

NBU 922-36F4BS / 36F4CS/ 36G4BS/ 36G4CS

Surface Use Plan of Operations Page 8

surface of the well site and access road. Where practical, the area will be ripped to a depth of 18 to 24 inches on 18 to 24-inch centers and surface materials will be pitted with small depressions to form longitudinal depressions 12 to 18 inches deep perpendicular to the natural flow of water.

All unnecessary surface equipment and structures (e.g. cattle guards) and water control structures (e.g. culverts, drainage pipes) not needed to facilitate successful reclamation will be removed during final reclamation. Roads that will be reclaimed will be ripped to a depth of 18 inches where practical, re-contoured to approximate the original contour of the ground and seeded.

Upon successfully completing reclamation of a P&A location, a Final Abandonment Notice will be submitted to UDOGM.

## Seeding and Measures Common to Interim and Final Reclamation

Reclaimed areas may be fenced to exclude grazing and encourage re-vegetation.

On slopes where severe erosion can become a problem and the use of machinery is not practical, seed will be hand broadcast and raked with twice the specified amount of seed. The slope will be stabilized using materials specifically designed to prevent erosion on steep slopes and hold seed in place so vegetation can become permanently established. These materials will include, but are not limited to, erosion control blankets and bonded fiber matrix at a rate to achieve a minimum of 80 percent soil coverage.

Seeding will occur year-round as conditions allow. Seed mixes appropriate to the native plant community as determined and specified for each project location based on the site specific soils will be used for revegetation. The site specific seed mix will be provided by SITLA.

## J. Surface/Mineral Ownership:

SITLA 675 East 500 South, Suite 500 Salt Lake City, UT 84102

## **K.** Other Information:

None

NBU 922-36F4BS / 36F4CS/ 36G4BS/ 36G4CS

## **Surface Use Plan of Operations**

Page 9

## M. <u>Lessee's or Operators' Representative & Certification:</u>

Gina T. Becker Regulatory Analyst II Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6086 Tommy Thompson General Manager, Drilling Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage for State lease activities is provided by State Surety Bond 22013542, and for applicable Federal lease activities and pursuant to 43 CFR 3104, by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Gina T. Becker

May 12, 2011

Date



JOE JOHNSON LANDMAN KERR-MCGEE ONSHORE OIL & GAS, L.P. 1099 18TH STREET, SUITE 1800 DENVER, CO 80202 720-929-6708 • FAX 720-929-7708 E-MAIL: JOE.JOHNSON@ANADARKO.COM

April 13, 2011

Ms. Diana Mason Division of Oil, Gas and Mining P.O. Box 145801 Salt Lake City, UT 84114-6100

Re: Directional Drilling R649-3-11

NBU 922-36G4BS

T9S-R22E

Section 36: SWNE/SWNE Surface: 2405' FNL, 2441' FEL Bottom Hole: 2235' FNL, 1818' FEL

Uintah County, Utah

Dear Ms. Mason:

Pursuant to the filing of Kerr-McGee Oil & Gas Onshore LP's (Kerr-McGee) Application for Permit to Drill regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to the Exception to Location and Siting of Wells.


- Kerr-McGee's NBU 922-36G4BS is located within the Natural Buttes Unit area.
- Kerr-McGee is permitting this well as a directional well in order to minimize surface disturbance. Locating the well at the surface location and directionally drilling from this location, Kerr-McGee will be able to utilize the existing road and pipelines in the area.
- Furthermore, Kerr-McGee certifies that it is the sole working interest owner within 460 feet of the entire
  directional well bore.

Therefore, based on the above stated information Kerr-McGee Oil & Gas Onshore LP requests the permit be granted pursuant to R649-3-11.

Sincerely,

KERR-MCGEE OIL & GAS ONSHORE LP

Joseph D. Johnson Landman



# **United States Department of the Interior**

## **BUREAU OF LAND MANAGEMENT**

Utah State Office P.O. Box 45155 Salt Lake City, Utah 84145-0155

IN REPLY REFER TO: 3160 (UT-922)

May 20, 2011

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2011 Plan of Development Natural Buttes Unit

Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2011 within the Natural Buttes Unit, Uintah County, Utah.

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE)

## NBU 922-36I PAD

43-047-51586	NBU	922-36H4BS BHL			_	0799 0494	
43-047-51587	NBU	922-36H4CS BHL			_	0792 0495	
43-047-51588	NBU	922-36I1CS BHL			_	0785 0494	
43-047-51589 NBU 922-36K PAI		922-36I4CS BHL			_	0805 0493	
		922-36K1BS BHL			_	1998 2148	
43-047-51591	NBU	922-36K1CS BHL				2015 2147	
43-047-51592	NBU	922-36K4BS BHL	 	 	 	2023 2147	
43-047-51593	NBU	922-36K4CS BHL				2006 2146	
43-047-51594	NBU	922-36L4CS BHL				1990 0821	

Page 2

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE

NRII	922	-3611	$P\Delta D$

NBU 922-36N PAI	)									
43-047-51595	NBU	922-36M1CS								
		BHL	Sec	36	T09S	R22E	0792	FSL	0816	FWL
12 047 51506	NIDII	000 201400	0	2.0	шоос	DOOR	1000	ПОТ	0070	T77.7T
43-047-51596	NBO	922-36M4CS			T095					
		рпг	sec	30	1095	RZZĒ	0132	LOL	0019	ГWL
43-047-51597	NRII	922-36N1BS	Sec	36	тпас	B22F	1088	FSI.	2379	FWT.
15 017 51557	INDO				T09S					
		2112	200	0 0	1030	11222	1200			
43-047-51598	NBU	922-36N4CS	Sec	36	T09S	R22E	1048	FSL	2379	FWL
		BHL	Sec	36	T09S	R22E	0190	FSL	2081	FWL
43-047-51599	NBU	922-3604CS	Sec	36	T09S	R22E	1058	FSL	2379	FWL
		BHL	Sec	36	T09S	R22E	0085	FSL	1814	FEL
NBU 922-360 PAI		000 007100	~	2.6	<b>TO 0 0</b>	D000	1045		0110	
43-04/-51600	NBU	922-36J1CS								
		RHT	sec	36	T09S	RZZE	2071	FSL	1809	FEL
13-017-51601	MRII	922-36J4BS	Sac	36	т∩ас	D22F	125/	FCI	2094	FFT
15 017 51001	INDO				T09S			_		
		DIIL	500	00	1030	11221	1,10	101	1010	
43-047-51602	NBU	922-36J4CS	Sec	36	T09S	R22E	1261	FSL	2075	FEL
		BHL	Sec	36	T09S	R22E	1409	FSL	1816	FEL
43-047-51603	NBU	922-3601BS	Sec	36	T09S	R22E	1257	FSL	2085	FEL
		BHL	Sec	36	T09S	R22E	1078	FSL	1815	FEL
43-047-51604	NBU	922-3604BS								
NDU 022 26D DAE	•	BHT	Sec	36	T09S	RZZE	0415	FSL	1814	FEL
NBU 922-36P PAI		922-36P1BS	202	36	π∩аς	D22F	1207	ECT	0606	CCT
45 047 51005	NDO				T09S					
		5115	DCC	50	1036	11221	1215	101	0195	1 1111
43-047-51606	NBU	922-36P1CS	Sec	36	T09S	R22E	1198	FSL	0611	FEL
		BHL	Sec	36	T09S	R22E	0911	FSL	0493	FEL
43-047-51607	NBU	922-36P4BS								
		BHL	Sec	36	T09S	R22E	0580	FSL	0493	FEL
10 015 51600		000 05-155	_						0.001	
43-04/-51608	NBU	922-36P4CS								
NBU 922-36B PAI	,	ВПГ	sec	36	T09S	KZZŁ	0243	FSL	0492	FEL
		922-36A1CS	Sec	36	T095	R22E	0678	FNT.	2273	FEI.
15 01, 51009	14110				T09S					
		2112		- 0					1	
43-047-51610	NBU	922-36B1CS	Sec	36	T09S	R22E	0674	FNL	2282	FEL
		BHL	Sec	36	T09S	R22E	0579	FNL	1821	FEL
43-047-51611	NBU	922-36B4BS								
		BHL	Sec	36	T09S	R22E	0905	Ŀ'NL	1828	Ͱ'EL

Page 3

API # WELL NAME LOCATION (Proposed PZ WASATCH-MESA VERDE BHL Sec 36 T09S R22E 1439 FNL 1861 FEL **NBU 922-36C PAD** BHL Sec 36 T09S R22E 0485 FNL 2152 FWL 43-047-51614 NBU 922-36C4BS Sec 36 T09S R22E 0706 FNL 1749 FWL BHL Sec 36 T09S R22E 0746 FNL 2153 FWL 43-047-51615 NBU 922-36F1BS Sec 36 T09S R22E 0718 FNL 1765 FWL BHL Sec 36 T09S R22E 1407 FNL 2151 FWL BHL Sec 36 T09S R22E 1738 FNL 2150 FWL **NBU 922-36D PAD** 43-047-51617 NBU 922-36D1CS Sec 36 T09S R22E 1062 FNL 0981 FWL BHL Sec 36 T09S R22E 0579 FNL 0825 FWL 43-047-51618 NBU 922-36D4BS Sec 36 T09S R22E 1060 FNL 0971 FWL BHL Sec 36 T09S R22E 0910 FNL 0825 FWL 43-047-51619 NBU 922-36D4CS Sec 36 T09S R22E 1064 FNL 0990 FWL BHL Sec 36 T09S R22E 1241 FNL 0825 FWL 43-047-51620 NBU 922-36E1BS Sec 36 T09S R22E 1067 FNL 1000 FWL BHL Sec 36 T09S R22E 1572 FNL 0825 FWL **NBU 922-36E PAD** BHL Sec 36 T09S R22E 1903 FNL 0824 FWL BHL Sec 36 T09S R22E 2245 FNL 0818 FWL BHL Sec 36 T09S R22E 2565 FNL 0824 FWL BHL Sec 36 T09S R22E 2401 FSL 0824 FWL **NBU 922-36G3 PAD** 43-047-51625 NBU 922-36F4BS Sec 36 T09S R22E 2414 FNL 2443 FEL BHL Sec 36 T09S R22E 2070 FNL 2149 FWL 43-047-51626 NBU 922-36F4CS Sec 36 T09S R22E 2424 FNL 2445 FEL BHL Sec 36 T09S R22E 2401 FNL 2149 FWL 43-047-51627 NBU 922-36G4BS Sec 36 T09S R22E 2405 FNL 2441 FEL BHL Sec 36 T09S R22E 2235 FNL 1818 FEL 

BHL Sec 36 T09S R22E 2566 FNL 1818 FEL

Page 4

This office has no objection to permitting the wells at this time.

Digitally signed by Michael L. Coulthard Michael L. Coulthard

Management, ou=Branch of Minerals, email=Michael\_Coulthard@blm.gov, c=US
Date: 2011.05.23 07:16:05-06'00'

bcc: File - Natural Buttes Unit

Division of Oil Gas and Mining

Central Files Agr. Sec. Chron Fluid Chron

MCoulthard:mc:5-20-11

From: Jim Davis

To: Bonner, Ed: Garrison, LaVonne: Hill, Brad: Mason, Diana

CC: Gina Becker; Lytle, Andy Date: 6/8/2011 3:00 PM

Subject: Kerr McGee APD approvals.

The following APDs have been approved by SITLA including arch and paleo clearance.

```
4304751586
             NBU 922-36H4BS
4304751587
             NBU 922-36H4CS
4304751588
             NBU 922-36I1CS
4304751589
             NBU 922-36I4CS
4304751590
             NBU 922-36K1BS
4304751591
             NBU 922-36K1CS
4304751592
             NBU 922-36K4BS
4304751593
             NBU 922-36K4CS
4304751594
             NBU 922-36L4CS
4304751595
             NBU 922-36M1CS
4304751596
             NBU 922-36M4CS
4304751597
             NBU 922-36N1BS
             NBU 922-36N4CS
4304751598
4304751599
             NBU 922-36O4CS
4304751600
             NBU 922-36J1CS
             NBU 922-36J4BS
4304751601
4304751602
             NBU 922-36J4CS
4304751603
             NBU 922-3601BS
4304751604
             NBU 922-36O4BS
4304751605
             NBU 922-36P1BS
4304751606
             NBU 922-36P1CS
4304751607
             NBU 922-36P4BS
4304751608
             NBU 922-36P4CS
4304751613
             NBU 922-36C1CS
4304751614
             NBU 922-36C4BS
4304751615
             NBU 922-36F1BS
             NBU 922-36F1CS
4304751616
             NBU 922-36D1CS
4304751617
4304751618
             NBU 922-36D4BS
4304751619
             NBU 922-36D4CS
4304751620
             NBU 922-36E1BS
4304751621
             NBU 922-36E1CS
4304751622
             NBU 922-36E4BS
4304751623
             NBU 922-36E4CS
4304751624
             NBU 922-36L1BS
4304751625
             NBU 922-36F4BS
4304751626
             NBU 922-36F4CS
4304751627
             NBU 922-36G4BS
4304751628
             NBU 922-36G4CS
```

Full paleo monitoring is a required condition for the approval of these APDs- as recommended in the paleo report.

```
4304751609
            NBU 922-36A1CS
4304751610
            NBU 922-36B1CS
4304751611
            NBU 922-36B4BS
4304751612
            NBU 922-36G1BS
```

Thanks.

-Jim


Jim Davis Utah Trust Lands Administration jimdavis1@utah.gov Phone: (801) 538-5156

## BOPE REVIEW KERR-MCGEE OIL & GAS ONSHORE, L.P. NBU 922-36G4BS 43047516270000

Well Name		KERR-MCGEE	E OIL	& GAS ON	ISH	ORE, L.P. NB	3U 922	2-36G4BS			
String		Surf	Pro	d							
Casing Size(")		8.625	4.50	00							
Setting Depth (TVD)		2220	867	78							
Previous Shoe Setting Dept	th (TVD)	40	222	20							
Max Mud Weight (ppg)		8.4	12.	5							
BOPE Proposed (psi)		500	500	00							
Casing Internal Yield (psi)		3390	778	80							
Operators Max Anticipate	5554	12.3	3								
Calculations	Surf String				8.62	5 "					
Max BHP (psi)	Sur	.052*Settir	ng De	epth*MV	V=	970					
4 /				1	٦	1370	BO	OPE Ade	quate For Drilling And Setting Casing at Depth?		
MASP (Gas) (psi)	Max	BHP-(0.12*)	Settii	ng Depth	)=	704	Ī N	0	air drill		
MASP (Gas/Mud) (psi)	Max	BHP-(0.22*)	Settii	ng Depth	)=	482	YI	ES	ОК		
						,	*(	Can Full	Expected Pressure Be Held At Previous Shoe?		
Pressure At Previous Shoe	Max BHP22*(Setting D	epth - Previou	ıs Sh	oe Depth	)=	490	N	0	Reasonable for area		
Required Casing/BOPE Te	est Pressure=					2220	psi	i			
*Max Pressure Allowed @	Previous Casing Shoe=					40	psi	psi *Assumes 1psi/ft frac gradient			
Calculations	Dwa	l String			_	4.50	Δ "				
Max BHP (psi)	1100	.052*Settir	ng Da	enth*MV	<i>J</i> =						
Will Dill (psi)		.032 Setti	ng D	epui ivi v	$\exists$	5641	BO	OPE Ade	quate For Drilling And Setting Casing at Depth?		
MASP (Gas) (psi)	Max	BHP-(0.12*)	Settii	ng Depth	)=	4600	-	ES I	1		
MASP (Gas/Mud) (psi)		BHP-(0.22*)			-	3732	#=	ES I	ОК		
						1,0.00			Expected Pressure Be Held At Previous Shoe?		
Pressure At Previous Shoe	Max BHP22*(Setting De	epth - Previou	ıs Sh	oe Depth	)=	4220	N	0	Reasonable		
Required Casing/BOPE To	st Pressure=					5000	psi	i			
*Max Pressure Allowed @	Previous Casing Shoe=					2220	psi	i *Assı	imes 1psi/ft frac gradient		
Calculations	C	·			_						
Max BHP (psi)	5	tring .052*Settir	ng Da	enth*MV	<i>J</i> =		+				
(psi)		.032 Setti	115 15	epui ivi v		<u> </u>	BO	OPE Ade	quate For Drilling And Setting Casing at Depth?		
MASP (Gas) (psi)	Max	x BHP-(0.12*)	Settii	ng Depth	)=		i N		1		
MASP (Gas/Mud) (psi)		BHP-(0.22*)			-	<u>'</u>	N				
					┪	<u> </u>	- 1		Expected Pressure Be Held At Previous Shoe?		
Pressure At Previous Shoe	Max BHP22*(Setting De	epth - Previou	ıs Sh	oe Depth	)=		N	0			
Required Casing/BOPE Te	st Pressure=						psi	i			
*Max Pressure Allowed @	Previous Casing Shoe=						psi	i *Assı	imes 1psi/ft frac gradient		
Calculations	S	tring					"				
Max BHP (psi)		.052*Setting Depth*MW=				1					
- /		2 1			l-	BO	OPE Ade	quate For Drilling And Setting Casing at Depth?			
MASP (Gas) (psi)	Max	x BHP-(0.12*Setting Depth)=				N	0				
MASP (Gas/Mud) (psi)	Max	BHP-(0.22*	Settii	ng Depth	)=		N	0			
							*(	Can Full	Expected Pressure Be Held At Previous Shoe?		
Pressure At Previous Shoe	Max BHP22*(Setting D	epth - Previou	ıs Sh	oe Depth	)=		N	0			
Required Casing/BOPE To	quired Casing/BOPE Test Pressure=						psi	i			

*Max Pressure Allowed @ Previous Casing Shoe=	psi	*Assumes 1psi/ft frac gradient

## 43047516270000 NBU 922-36G4BS



Well name:

43047516270000 NBU 922-36G4BS

Operator:

KERR-MCGEE OIL & GAS ONSHORE, L.P.

String type:

Surface

Project ID: 43-047-51627

Location:

**UINTAH** 

COUNTY

**Environment:** Minimum design factors:

**Collapse** 

Mud weight: 8.400 ppg Design is based on evacuated pipe.

Collapse: Design factor

H2S considered?

No 74 °F

1.125

Surface temperature: Bottom hole temperature:

105 °F

Temperature gradient: Minimum section length: 1.40 °F/100ft 100 ft

Burşt:

Design factor

1.00

Cement top:

Kick-off point

1,172 ft

300 ft

451 ft

16.75°

2 °/100ft

**Burst** 

Max anticipated surface

No backup mud specified.

pressure: Internal gradient: Calculated BHP

Design parameters:

2,006 psi 0.120 psi/ft

2,273 psi

**Tension:** 8 Round STC:

Neutral point:

8 Round LTC: Buttress:

1.60 (J) Premium: Body yield:

1.50 (J) 1.50 (B)

1,993 ft

1.80 (J)

1.70 (J)

Tension is based on air weight. Next mud weight:

Inclination at shoe: Re subsequent strings: Next setting depth:

Departure at shoe:

Maximum dogleg:

Directional Info - Build & Drop

8,760 ft 12.500 ppg

Next setting BHP: Fracture mud wt: Fracture depth: Injection pressure:

5,688 psi 19.250 ppg 2,280 ft 2,280 psi

Run	Segment		Nominal		End	True Vert	Measured	Drift	Est.
Seq	Length (ft)	Size (in)	Weight (lbs/ft)	Grade	Finish	Depth (ft)	Depth (ft)	Diameter (in)	Cost (\$)
1	2280	8.625	28.00	I-55	LT&C	2220	2280	7.892	90288
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	969	1880	1.941	2273	3390	1.49	62.2	348	5.60 J

Prepared

by:

Helen Sadik-Macdonald

Div of Oil, Gas & Mining

Phone: 801 538-5357 FAX: 801-359-3940

Date: July 21,2011 Salt Lake City, Utah

Collapse is based on a vertical depth of 2220 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Well name:

43047516270000 NBU 922-36G4BS

Operator:

KERR-MCGEE OIL & GAS ONSHORE, L.P.

Location:

Production

**UINTAH** 

Project ID:

String type:

COUNTY

43-047-51627

Design parameters:

**Collapse** 

Mud weight: Design is based on evacuated pipe.

12.500 ppg

Minimum design factors: Collapse:

Design factor

**Environment:** 

H2S considered? Surface temperature:

No 74 °F 195 °F

Bottom hole temperature: Temperature gradient:

1.40 °F/100ft

Minimum section length:

100 ft

**Burst:** 

Design factor

1.00

1.125

Cement top:

777 ft

Burst

Max anticipated surface

pressure: Internal gradient: Calculated BHP

3,726 psi 0.220 psi/ft

5,635 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J) 8 Round LTC: 1.80 (J) Buttress: 1.60 (J)

Premium:

Body yield:

1.50 (J) 1.60 (B) Directional Info - Build & Drop

Kick-off point Departure at shoe: Maximum dogleg:

300 ft 644 ft 2 °/100ft

Inclination at shoe:

o°

Tension is based on air weight.

Neutral point:

7,138 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	8760	4.5	11.60	I-80	LT&C	8678	8760	3.875	115632
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	5635	6360	1.129	5635	7780	1.38	100.7	212	2.11 J

Prepared

by:

Helen Sadik-Macdonald

Div of Oil, Gas & Mining

Phone: 801 538-5357 FAX: 801-359-3940

Date: July 21,2011 Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 8678 ft, a mud weight of 12.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

## **ON-SITE PREDRILL EVALUATION**

## Utah Division of Oil, Gas and Mining

**Operator** KERR-MCGEE OIL & GAS ONSHORE, L.P.

Well Name NBU 922-36G4BS

API Number 43047516270000 APD No 3801 Field/Unit NATURAL BUTTES

**Location: 1/4,1/4** SWNE **Sec** 36 **Tw** 9.0S **Rng** 22.0E 2405 FNL 2441 FEL

GPS Coord (UTM) 637636 4428031 Surface Owner

## **Participants**

Floyd Bartlett (DOGM), Sheila Wopsock, Lovell Young, Gina Becker, Mark Koehn, Griz Oleen (Kerr McGee), Ben Williams (UDWR) and Mitch Batty, John Slaugh (Timberline Engineering and Land Surveying).

## Regional/Local Setting & Topography

The general area is in the southeast portion of the Natural Buttes Unit, which contains the White River and rugged drainages that drain into the White River. Topography is varied and frequently dissected by short draws or washes, which become overly steep as they approach the White River breaks or rim. Distance to the White River varies from <sup>3</sup>/<sub>4</sub> mile to 2 miles. The side drainages are dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. Vernal, Utah is approximately 42 air miles to the northwest. Access from Vernal is approximately 45.6 road miles following Utah State, Uintah County and oilfield development roads to the location.

Four additional gas wells will be added to and directionally drilled from the NBU 922-36G3 pad. They are the NBU 922-36G4BS, NBU 922-36F4BS, NBU 922-36F4CS and NBU 922-36G4CS. The pad contains the existing NBU 932-36G producing gas well. The existing pad will be significantly enlarged in all directions. The site is in rough terrain. Numerous draws and steep rocky hills occur. Moderate excavation will be required to enlarge the pad. The site is on the point or end of a ridge which has been leveled for the existing pad. The reserve pit will be expanded to the west with the spoils located in a moderately wide swale or valley. The spoils will be recoverable. A drainage to the east will be filled and a diversion constructed off the pad on the north and east side. Cut for the reserve pit at corner C is 26.7 feet. Where the pad is cut into the steep side slopes, the cut slope may be left at about ½:1 to reduce the amount of cutting and disturbance. The south end of the pit is in 3.1 feet of fill. With the proposed 15 foot outer bench, 2 feet of freeboard, a 30-mil liner and the spoils placed along this side, it should be stable. The existing pad shows no stability problems. Although heavy excavation is required for enlarging the pad, no stability concerns exist. The selected site is the only suitable location in the immediate area.

Both the surface and minerals are owned by SITLA.

## Surface Use Plan

**Current Surface Use** 

Grazing
Wildlfe Habitat
Existing Well Pad

New Road Miles Well Pad Src Const Material Surface Formation

0 Width 352 Length 455 Onsite UNTA

**Ancillary Facilities** N

### **Waste Management Plan Adequate?**

## **Environmental Parameters**

8/3/2011 Page 1

## Affected Floodplains and/or Wetlands N

## Flora / Fauna

Area beyond the existing pad is poorly vegetated with greasewood, cheatgrass, black sagebrush, broom snakeweed, globemallow, Sitanion hystrix, shadscale, rabbitbrush, loco weed, pepper weed, halogeton and annuals.

Sheep, deer, antelope, coyote, and other small mammals and birds.

## Soil Type and Characteristics

Rocky sandy loam.

#### **Erosion Issues** Y

A drainage to the east will be filled and a diversion constructed off the pad on the north and east side.

#### **Sedimentation Issues** N

## Site Stability Issues N

## **Drainage Diverson Required?** Y

A drainage to the east will be filled and a diversion constructed off the pad on the north and east side.

## Berm Required? N

## **Erosion Sedimentation Control Required?** Y

A drainage to the east will be filled and a diversion constructed off the pad on the north and east side.

Paleo Survey Run? Paleo Potental Observed? Y Cultural Survey Run? Y Cultural Resources? N

## **Reserve Pit**

Site-Specific Factors	Site R		
Distance to Groundwater (feet)	100 to 200	5	
Distance to Surface Water (feet)	>1000	0	
Dist. Nearest Municipal Well (ft)	>5280	0	
Distance to Other Wells (feet)		20	
Native Soil Type	Mod permeability	10	
Fluid Type	Fresh Water	5	
Drill Cuttings	Normal Rock	0	
<b>Annual Precipitation (inches)</b>		0	
Affected Populations			
<b>Presence Nearby Utility Conduits</b>	Not Present	0	
	Final Score	40	1 Sensitivity Level

## **Characteristics / Requirements**

The reserve pit is planned mostly in an area of cut in the southwest side of the location. Dimensions are 120' x 260' x 12' deep with 2' of freeboard. The south end of the pit is in 3.1 feet of fill. With the proposed 15 foot outer bench, 2 feet of freeboard, a 30-mil liner and the spoils placed along this side, it should be stable.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 30 Pit Underlayment Required? Y

8/3/2011 Page 2

## **Other Observations / Comments**

Floyd Bartlett 5/24/2011 **Evaluator Date / Time** 

8/3/2011 Page 3

# **Application for Permit to Drill Statement of Basis**

**Utah Division of Oil, Gas and Mining** 

Page 1

APD No	API WellN	o			Statu	s W	ell Type	Surf Own	er CBM
3801	430475162	70000			SITL	A G	W	S	No
Operator	KERR-MC	GEE C	IL & (	GAS	ONSHORE	, L.P. Su	ırface Owner-APD		
Well Name	NBU 922-3	6G4BS	S			Uı	nit	NATURA	L BUTTES
Field	NATURAL	BUT	ΓES			Ty	pe of Work	DRILL	
Location	SWNE 36	5 9S	22E	S	2405 FNL	2441 FEL	GPS Coord (UTM)	637702E	4428040N
		_							

## **Geologic Statement of Basis**

8/3/2011

Kerr McGee proposes to set 2,280' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 2,950'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the proposed location . The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The production casing cement should be brought up above the base of the moderately saline ground water in order to isolate it from fresher waters up hole. The proposed casing and cement should adequately protect any usable ground water.

Brad Hill 6/21/2011
APD Evaluator Date / Time

## **Surface Statement of Basis**

The general area is in the southeast portion of the Natural Buttes Unit, which contains the White River and rugged drainages that drain into the White River. Topography is varied and frequently dissected by short draws or washes, which become overly steep as they approach the White River breaks or rim. Distance to the White River varies from ¾ mile to 2 miles. The side drainages are dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. Vernal, Utah is approximately 42 air miles to the northwest. Access from Vernal is approximately 45.6 road miles following Utah State, Uintah County and oilfield development roads to the location.

Four additional gas wells will be added to and directionally drilled from the NBU 922-36G3 pad. They are the NBU 922-36G4BS, NBU 922-36F4BS, NBU 922-36F4CS and NBU 922-36G4CS. The pad contains the existing NBU 932-36G producing gas well. The existing pad will be significantly enlarged in all directions. The site is in rough terrain. Numerous draws and steep rocky hills occur. Moderate excavation will be required to enlarge the pad. The site is on the point or end of a ridge which has been leveled for the existing pad. The reserve pit will be expanded to the west with the spoils located in a moderately wide swale or valley. The spoils will be recoverable. A drainage to the east will be filled and a diversion constructed off the pad on the north and east side. Cut for the reserve pit at corner C is 26.7 feet. Where the pad is cut into the steep side slopes, the cut slope may be left at about ½:1 to reduce the amount of cutting and disturbance. The south end of the pit is in 3.1 feet of fill. With the proposed 15 foot outer bench, 2 feet of freeboard, a 30-mil liner and the spoils placed along this side, it should be stable. The existing pad shows no stability problems. Although heavy excavation is required for enlarging the pad, no stability concerns exist. The selected site is the only suitable location in the immediate area.

Both the surface and minerals are owned by SITLA. Ed Bonner and Jim Davis of SITLA were invited to attend the pre-site evaluation. Neither attended. SITLA is to be contacted for reclamation standards including a seed mix to be used.

Ben Williams of the Utah Division of Wildlife Resources attended the pre-site. Mr. Williams stated no wildlife

# **Application for Permit to Drill Statement of Basis**

Utah Division of Oil, Gas and Mining

Page 2

values would be significantly affected by drilling and operating the additional wells at this location.

Floyd Bartlett 5/24/2011
Onsite Evaluator Date / Time

## **Conditions of Approval / Application for Permit to Drill**

**Category** Condition

8/3/2011

Pits A synthetic liner with a minimum thickness of 30 mils with a double felt subliner shall be properly installed and

maintained in the reserve pit.

Surface Drainages adjacent to the proposed pad shall be diverted around the location. Surface The reserve pit shall be fenced upon completion of drilling operations.

## WORKSHEET APPLICATION FOR PERMIT TO DRILL

**APD RECEIVED:** 5/13/2011 **API NO. ASSIGNED:** 43047516270000

WELL NAME: NBU 922-36G4BS

**OPERATOR:** KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995) **PHONE NUMBER:** 720 929-6086

**CONTACT:** Gina Becker

PROPOSED LOCATION: SWNE 36 090S 220E **Permit Tech Review:** 

> SURFACE: 2405 FNL 2441 FEL **Engineering Review:**

> **BOTTOM:** 2235 FNL 1818 FEL Geology Review:

**COUNTY: UINTAH** 

**LATITUDE:** 39.99322 **LONGITUDE:** -109.38704

UTM SURF EASTINGS: 637702.00 NORTHINGS: 4428040.00

FIELD NAME: NATURAL BUTTES

LEASE TYPE: 3 - State

LEASE NUMBER: ML-22650 PROPOSED PRODUCING FORMATION(S): WASATCH-MESA VERDE

**SURFACE OWNER: 3 - State COALBED METHANE: NO** 

**RECEIVED AND/OR REVIEWED: LOCATION AND SITING:** 

 PLAT R649-2-3.

Unit: NATURAL BUTTES Bond: STATE/FEE - 22013542

**Potash** R649-3-2. General

Oil Shale 190-5

Oil Shale 190-3 R649-3-3. Exception

**Drilling Unit** Oil Shale 190-13

Board Cause No: Cause 173-14 Water Permit: Permit #43-8496

**Effective Date:** 12/2/1999 **RDCC Review:** 

Siting: Suspends General Siting **Fee Surface Agreement** 

✓ Intent to Commingle R649-3-11. Directional Drill

**Commingling Approved** 

**Comments:** Presite Completed

Stipulations:

3 - Commingling - ddoucet 5 - Statement of Basis - bhill 15 - Directional - dmason 17 - Oil Shale 190-5(b) - dmason 25 - Surface Casing - hmacdonald

API Well No: 43047516270000



## State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

## Permit To Drill

\*\*\*\*\*\*

**Well Name:** NBU 922-36G4BS **API Well Number:** 43047516270000

**Lease Number:** ML-22650 **Surface Owner:** STATE **Approval Date:** 8/3/2011

#### **Issued to:**

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

## **Authority:**

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14. The expected producing formation or pool is the WASATCH-MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

#### **Duration:**

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

## **Commingle:**

In accordance with Board Cause No. 173-14, commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

#### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

## **Conditions of Approval:**

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Surface casing shall be cemented to the surface.

API Well No: 43047516270000

## **Additional Approvals:**

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan contact Dustin Doucet
- Significant plug back of the well contact Dustin Doucet
- Plug and abandonment of the well contact Dustin Doucet

## **Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well contact Carol Daniels OR
- submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at http://oilgas.ogm.utah.gov
- 24 hours prior to testing blowout prevention equipment contact Dan Jarvis
- 24 hours prior to cementing or testing casing contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well contact Dan Jarvis

## **Contact Information:**

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 office
- Dustin Doucet 801-538-5281 office

801-733-0983 - after office hours

• Dan Jarvis 801-538-5338 - office

801-231-8956 - after office hours

## **Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) due within 5 days of spudding the well
- Monthly Status Report (Form 9) due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) due prior to implementation
- Written Notice of Emergency Changes (Form 9) due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) due prior to implementation
- Report of Water Encountered (Form 7) due within 30 days after completion
- Well Completion Report (Form 8) due within 30 days after completion or plugging

Approved By:

For John Rogers Associate Director, Oil & Gas

## BLM - Vernal Field Office - Notification Form

Operator KERR-McGEE OIL & GAS Rig Name/# BUCKET RIG							
	nitted By SHEILA WOPSOCK		nber <u>435</u>	5.781.7024			
	Name/Number NBU 922-360			Danga oor			
	Qtr <u>SW/NE</u> Section <u>36</u> e Serial Number <u>ML-22650</u>	. rownsnip <u>s</u>	<u> </u>	Range <u>22E</u>			
	Vumber <u>4304751627</u>						
/ (I I )	4304731027						
Spud	<u> Notice</u> – Spud is the initia	l spudding o	of the we	ell, not drilling			
out b	pelow a casing string.						
	Date/Time <u>11/01/2011</u>	0800 HRS	AM 🗸	РМ 🗌			
<u>Casir</u>	<u>ng</u> – Please report time cas	ing run starl	ts, not c	ementing			
	Surface Casing		1	RECEIVED			
	Intermediate Casing			OCT 2 8 2011			
	Production Casing		DIV I	OF OIL, GAS & MINING			
	Liner		Second Sec. 5	on the two transfers			
	Other						
	Date/Time <u>11/21/2011</u>	0800 HRS	AM 🔽	РМ			
BOPE	= =						
	Initial BOPE test at surface	casing poir	nt				
	BOPE test at intermediate	casing point	-				
	30 day BOPE test						
	Other						
	Date/Time		AM 🗌	РМ			
Rema	arks ESTIMATED DATE AND	TIME. PLEA <del>781.7051 FO</del>	SE CON	TACT			
				_			

Sundry Number: 19949 API Well Number: 43047516270000

			FORM 9			
	STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES					
	DIVISION OF OIL, GAS, AND MININ	G	<b>5.LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-22650			
SUNDF	RY NOTICES AND REPORTS O	N WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
	sals to drill new wells, significantly deepen exi gged wells, or to drill horizontal laterals. Use		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36G4BS			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSI	HORE, L.P.		9. API NUMBER: 43047516270000			
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th S	PHONE I treet, Suite 600, Denver, CO, 80217 3779	NUMBER: 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2405 FNL 2441 FEL			COUNTY: UINTAH			
QTR/QTR, SECTION, TOWNSHI Qtr/Qtr: SWNE Section: 36	P, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian: S		STATE: UTAH			
11. CHE	CK APPROPRIATE BOXES TO INDICATE I	NATURE OF NOTICE, REPORT,	OR OTHER DATA			
TYPE OF SUBMISSION		TYPE OF ACTION				
	☐ ACIDIZE ☐	ALTER CASING	☐ CASING REPAIR			
NOTICE OF INTENT Approximate date work will start:	$\Box$ Change to previous plans $\Box$	CHANGE TUBING	☐ CHANGE WELL NAME			
Approximate date work will start.	☐ CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	☐ CONVERT WELL TYPE			
SUBSEQUENT REPORT Date of Work Completion:	☐ DEEPEN ☐	FRACTURE TREAT	☐ NEW CONSTRUCTION			
	☐ OPERATOR CHANGE	PLUG AND ABANDON	☐ PLUG BACK			
✓ SPUD REPORT	$\square$ production start or resume $\square$	RECLAMATION OF WELL SITE	☐ RECOMPLETE DIFFERENT FORMATION			
Date of Spud: 11/1/2011	☐ REPERFORATE CURRENT FORMATION ☐	SIDETRACK TO REPAIR WELL	☐ TEMPORARY ABANDON			
	☐ TUBING REPAIR ☐	VENT OR FLARE	☐ WATER DISPOSAL			
DRILLING REPORT Report Date:	☐ WATER SHUTOFF ☐	SI TA STATUS EXTENSION	APD EXTENSION			
	☐ WILDCAT WELL DETERMINATION ☐	OTHER	OTHER:			
	MPLETED OPERATIONS. Clearly show all pertine BUCKET RIG. DRILLED 20" CON	•	,			
RAN 14" 36.7# SCHE	DULE 10 PIPE. CMT W/28 SX RE					
	11/01/2011 AT 1200 HRS.		Accepted by the Utah Division of			
			, Gas and Mining			
			RECORD ONLY			
		1 01	RECORD GIALI			
NAME (PLEASE PRINT) Sheila Wopsock	<b>PHONE NUMBER</b> 435 781-7024	TITLE Regulatory Analyst				
SIGNATURE		DATE 11/2/2011				
N/A		11/2/2011				

Sundry Number: 19627 API Well Number: 43047516270000

	STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES		FORM 9				
	DIVISION OF OIL, GAS, AND MINING	3	<b>5.LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-22650				
SUNDF	RY NOTICES AND REPORTS ON	I WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:				
Do not use this form for proposottom-hole depth, reenter plu DRILL form for such proposals.	sals to drill new wells, significantly deepen exist igged wells, or to drill horizontal laterals. Use A	ting wells below current PPLICATION FOR PERMIT TO	7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES				
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36G4BS				
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	<b>9. API NUMBER:</b> 43047516270000						
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th S	PHONE Notes: Suite 600, Denver, CO, 80217 3779	UMBER: 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES				
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2405 FNL 2441 FEL		COUNTY: UINTAH					
QTR/QTR, SECTION, TOWNSHI Qtr/Qtr: SWNE Section: 36	rp, range, meridian: Township: 09.0S Range: 22.0E Meridian: S		STATE: UTAH				
11. CHE	CK APPROPRIATE BOXES TO INDICATE N	ATURE OF NOTICE, REPORT,	OR OTHER DATA				
TYPE OF SUBMISSION		TYPE OF ACTION					
The Operator reques	CHANGE WELL STATUS  DEEPEN  OPERATOR CHANGE  PRODUCTION START OR RESUME  REPERFORATE CURRENT FORMATION  TUBING REPAIR  WATER SHUTOFF  WILDCAT WELL DETERMINATION  OMPLETED OPERATIONS. Clearly show all pertinents approval for changes in the dr	illing plan. Specifically,	CHANGE WELL NAME  CONVERT WELL TYPE  NEW CONSTRUCTION  PLUG BACK  RECOMPLETE DIFFERENT FORMATION  TEMPORARY ABANDON  WATER DISPOSAL  APD EXTENSION  OTHER:				
The Operator requests approval for changes in the drilling plan. Specifically, the Operator requests approval for a FIT waiver, closed loop drilling options, and a production casing change. The production casing change includes a switch from 4-1/2" I-80 11.6 LB BTC/LTC casing to 4-1/2" I-80 11.6 LB Ultra DQX/LTC casing. All other aspects of the previously approved drilling plan will not change. These proposals do not deviate from previously submitted and approved plans. Please see attachments. Thank you.  By:    Approved by the Utah Division of Oil, Gas and Mining   11/10/2011   11/1							
NAME (PLEASE PRINT) Andy Lytle	<b>PHONE NUMBER</b> 720 929-6100	Regulatory Analyst					
<b>SIGNATURE</b> N/A		<b>DATE</b> 10/19/2011					

Sundry Number: 19627 API Well Number: 43047516270000

## **Requested Drilling Changes:**

## **Closed Loop**

Kerr-McGee will use either a closed loop drilling system that will require one pit and one cuttings storage area to be constructed on the drilling pad or a traditional drilling operation with one pit used for drilling and completion operations. The cuttings storage area will be used to contain only the de-watered drill cuttings and will be lined and bermed to prevent any liquid runoff. The drill cuttings will be buried in the completion pit once completion operations are completed according to traditional pit closure standards. The pit will be constructed to allow for completion operations. The completion operations pit will be lined with a synthetic material 20 mil or thicker and will be used for the completing of the wells on the pad or used as part of our Aandarko Completions Transportation System (ACTS). Using the closed loop drilling system will allow Kerr-McGee to decrease the amount of disturbance/footprint on location compared to a single large drilling/completions pit.

If Kerr-McGee does not use a closed loop drilling system, it will construct a traditional drilling/completions pit to contain drill cuttings and for use in completion operations. The pit will be lined with a synthetic material 20 mil or thicker. The drill cuttings will be buried in the pit using traditional pit closure standards.

## **Variance for FIT Requirements**

Kerr-McGee requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

Sundry Number: 20531 API Well Number: 43047516270000

	STATE OF UTAH DEPARTMENT OF NATURAL RESOURCE		FORM 9		
	5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650				
SUND	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:				
	sals to drill new wells, significantly deepen gged wells, or to drill horizontal laterals. Us		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES		
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36G4BS		
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	HORE, L.P.		9. API NUMBER: 43047516270000		
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th S	PHON treet, Suite 600, Denver, CO, 80217 3779	NE NUMBER: 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES		
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2405 FNL 2441 FEL			COUNTY: UINTAH		
QTR/QTR, SECTION, TOWNSHI Qtr/Qtr: SWNE Section: 36	IP, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian: S	5	STATE: UTAH		
11. CHE	CK APPROPRIATE BOXES TO INDICAT	E NATURE OF NOTICE, REPORT,	OR OTHER DATA		
TYPE OF SUBMISSION		TYPE OF ACTION			
MIRU AIR RIG ON N SURFACE CASING	CHANGE TO PREVIOUS PLANS CHANGE WELL STATUS DEEPEN OPERATOR CHANGE PRODUCTION START OR RESUME REPERFORATE CURRENT FORMATION TUBING REPAIR WATER SHUTOFF WILDCAT WELL DETERMINATION MPLETED OPERATIONS. Clearly show all pert	ACE HOLE TO 2482'. RAN ITING ON ROTARY RIG. ITH WELL COMPLETION A U			
NAME (PLEASE PRINT)	PHONE NUMBER	TITLE  Decidentary Applyet			
Jaime Scharnowske  SIGNATURE	720 929-6304	Regulartory Analyst  DATE			
N/A		11/21/2011			

### STATE OF UTAH **DEPARTMENT OF NATURAL RESOURCES** DIVISION OF OIL, GAS AND MINING

## **ENTITY ACTION FORM**

zip 84078

Operator:

KERR McGEE OIL & GAS ONSHORE LP

Operator Account Number: N 2995

Address:

1368 SOUTH 1200 EAST

city VERNAL

state UT

Phone Number: <u>(435)</u> 781-7024

Well 1

API Number	Well	Name	QQ Sec Twp		Rng County 22E UINTAH  Entity Assignment Effective Date		
4304751627	NBU 922-36G4BS	922-36G4BS		SWNE 36 9S			
Action Code	Current Entity Number	New Entity Number	Spud Date				
В	99999	3900	10/1/2011				
Comments: MIRU SPU	J PETE MARTIN BUCK D WELL ON 11/01/2011	ET RIG. WSM I AT 1200 HRS.	1VD B+	46=	SW	NE	

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304750778	NBU 921-8K	BU 921-8K		NESW 8 9S		21E UINTAH	
Action Code	Current Entity Number	New Entity Number	S	Spud Date		Entity Assignment Effective Date	
β	99999	2900	10/31/2011		11/9/11		
	J PETE MARTIN BUCK D WELL ON 10/31/201		HK= 77	IVRC	$>= \omega$ .	SMV.	b

Well 3

API Number	Well	Name	QQ	Sec	Twp	Rng	County
4304750734	NBU 921-8N		SESW	8	98	21E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
B	99999	2900	11/1/2011		11	1/9/11	
MIRU PETE MARTIN BUCKET RIG. BLKHK = MVRD = WSMVD SPUD WELL ON 11/01/2011 AT 1030 HRS.							

#### **ACTION CODES:**

- A Establish new entity for new well (single well only)
- B Add new well to existing entity (group or unit well)
- Re-assign well from one existing entity to another existing entity
- D Re-assign well from one existing entity to a new entity
- E Other (Explain in 'comments' section)

SHEILA WOPSOCK

Signature **REGULATORY ANALYST** 

11/1/2011 Date

(6/2000)

RECEIVED NOV 0 2 2011

# State of Utah - Notification Form

Operator <u>Anadarko Petroleum</u> Rig Name/# <u>Ensign 139</u>
Submitted By KENNY MORRIS Phone Number
435- 828-0984
Well Name/Number NBU 922-36G4BS
Qtr/Qtr SW/NE Section 36 Township 9S Range 22E
Lease Serial Number ML-22650
API Number43047516270000
APT Nulliber
<u>Casing</u> – Time casing run starts, not cementing times.
Production Casing Other
Date/Time AM PM
BOPE
Initial BOPE test at surface casing point Other
D . (T) 42/24/2044 0000 AM M DM
Date/Time <u>12/31/2011</u> <u>0600</u> AM ⊠ PM □
Dir Mayo
Rig Move
Location To:
Date/Time AM PM
Remarks WILL BOP TEST EARLY SATURDAY

# State of Utah - Notification Form

Ope	rator <u>Anadarko Petroleum</u> Rig Name/# .	Ensign 139
Subr	mitted By KENNY MORRIS	Phone Number
	<u>828-0984</u>	
Well	Name/Number NBU 922-36G4BS	
Qtr/0	Qtr <u>SW/NE</u> Section <u>36</u> Township <u>9S</u>	Range 22E
Leas	se Serial Number <u>ML-22650</u>	
API	Number43047516270000	
<u>Casi</u>	<u>ng</u> – Time casing run starts, not cementin	g times.
	Duado ation Casina	
Ä	Production Casing	
	Other	
	Date/Time <u>1/4/2012</u> <u>11:00</u> AM	РМ 🗍
	Date/ Time <u>1/ 1/2012</u> <u>11:00</u> / 11	· · · · <u></u>
BOP	E	DEOEU/ED
	Initial BOPE test at surface casing point	RECEIVED
	Other	JAN 0 3 2012
		DIV. OF OIL, GAS F Section
	Date/Time AM PM D	
Rig I	<u>Move</u>	
Loca	tion To:	
	Date/Time AM P	М 🔛
_		N CCC WEDNECDAY
	arks WILL RUN & CEMENT PRODUCTION	N COG WEDINESDAY
MOR	RNING	
		·

Sundry Number: 21735 API Well Number: 43047516270000

	FORM 9					
	<b>5.LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-22650					
SUNDF	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:					
	sals to drill new wells, significantly deepen exis Igged wells, or to drill horizontal laterals. Use A		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36G4BS			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	HORE, L.P.		9. API NUMBER: 43047516270000			
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th S	PHONE N treet, Suite 600, Denver, CO, 80217 3779	UMBER: 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2405 FNL 2441 FEL			COUNTY: UINTAH			
QTR/QTR, SECTION, TOWNSHI	P, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian: S		STATE: UTAH			
11. CHE	CK APPROPRIATE BOXES TO INDICATE N	ATURE OF NOTICE, REPORT,	OR OTHER DATA			
TYPE OF SUBMISSION		TYPE OF ACTION				
	ACIDIZE	ALTER CASING	CASING REPAIR			
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME			
✓ SUBSEQUENT REPORT		COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE			
Date of Work Completion:		FRACTURE TREAT	☐ NEW CONSTRUCTION			
	☐ PRODUCTION START OR RESUME	PLUG AND ABANDON RECLAMATION OF WELL SITE	☐ PLUG BACK☐ RECOMPLETE DIFFERENT FORMATION			
SPUD REPORT Date of Spud:		SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON			
		VENT OR FLARE	☐ WATER DISPOSAL			
DRILLING REPORT Report Date:	☐ WATER SHUTOFF ☐	SI TA STATUS EXTENSION	☐ APD EXTENSION			
	☐ WILDCAT WELL DETERMINATION ✓	OTHER	OTHER: RIG REL ACTS PIT			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  MIRU ROTARY RIG. FINISHED DRILLING FROM 2482′ TO 8770′ ON JAN. 3,  2012. RAN 4-1/2″ 11.6# I-80 PRODUCTION CASING. CEMENTED  PRODUCTION CASING. RELEASED ENSIGN RIG 139 ON JAN. 5, 2012 @ 06:00  HRS. DETAILS OF CEMENT JOB WILL BE INCLUDED WITH THE WELL  COMPLETION REPORT. WELL IS WAITING ON FINAL COMPLETION ACTIVITIES.  THE PIT ON THIS LOCATION WILL BE REFURBISHED AND UTILIZED AS PART  OF THE ACTS SYSTEM.  By:						
NAME (PLEASE PRINT) Jaime Scharnowske	<b>PHONE NUMBER</b> 720 929-6304	TITLE Regulartory Analyst				
SIGNATURE N/A		DATE 1/5/2012				

Sundry Number: 23134 API Well Number: 43047516270000

	FORM 9					
ı	5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650					
SUNDR	RY NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
	posals to drill new wells, significantly reenter plugged wells, or to drill horizo n for such proposals.		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36G4BS			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	ISHORE, L.P.		9. API NUMBER: 43047516270000			
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th	h Street, Suite 600, Denver, CO, 8021	<b>PHONE NUMBER:</b> 73779 720 929-6	9. FIELD and POOL or WILDCAT: 5NATERAL BUTTES			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2405 FNL 2441 FEL			COUNTY: UINTAH			
QTR/QTR, SECTION, TOWNSH Qtr/Qtr: SWNE Section: 3	HIP, RANGE, MERIDIAN: 36 Township: 09.0S Range: 22.0E Merio	dian: S	STATE: UTAH			
11. CHECI	K APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA			
TYPE OF SUBMISSION		TYPE OF ACTION				
	ACIDIZE	ALTER CASING	CASING REPAIR			
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME			
	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE			
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	☐ NEW CONSTRUCTION			
	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK			
SPUD REPORT	✓ PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION			
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON			
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL			
DRILLING REPORT     Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION			
2/15/2012	WILDCAT WELL DETERMINATION	OTHER	OTHER:			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  THE SUBJECT WELL WAS PLACED ON PRODUCTION ON 02/15/2012 AT 1715 HRS. THE CHRONOLOGICAL WELL HISTORY WILL BE SUBMITTED WITH THE WELL COMPLETION REPORT.  Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY February 16, 2012						
NAME (PLEASE PRINT) Sheila Wopsock	PHONE NUMB 435 781-7024	ER TITLE Regulatory Analyst				
SIGNATURE	433 / 01-/ 024	DATE				
N/A		2/16/2012				

#### STATE OF UTAH

				RTMEN	TATE ( TOF NA FOIL,	TURA	L RESO						(hi 5. L	ghlight EASE DE	chan SIGN/	ATION AN		FO	ORM 8 BER:
														ML 22		TTEE OF	TRIF	E NAME	
1a. TYPE OF WELL	L COMF						ETIC	N R	EPOF	RT AND	LOG								
b. TYPE OF WOR		W		] ;	GAS WELL <b>Z</b>	7	DRY [		ОТН	ER			- [	UTU6	304				
NEW WELL 2	HORIZ. LATS.	DI Ei	EEP-	]	RE- ENTRY	]	DIFF. RESVR.	]	отн	ER		-		NBU	922-	<sup>4</sup> NUMBE -36G4			
KERR MC	GEE OIL	. & GA	S ON	ISHOF	RE, L.F	·.								PI NUME 43047		527			
P.O.BOX 1	73779		ITY DE	NVEF	₹	STATE	СО	ZIP <b>802</b>	217		NUMBER: 20) 929-	6304				DL, OR W L BUT			
4. LOCATION OF W AT SURFACE:			NL 24	41 FE	L S36	,T9S,I	R22E							QTR/QTI MERIDIA WNE				HIP, RANG	
AT TOP PRODU	CING INTERVA	AL REPO	RTED BE	LOW: S	SWNE	2225	FNL 1	826 F						7714	00	, 50		221 0	,
AT TOTAL DEPT					FEL S	36,T9	S,R22	E	BH	L by	HENN	J	1	COUNTY			13	B. STATE	UTAH
14. DATE SPUDDED: 15. DATE T.D. REACHED: 16. DATE COMPLETED: 1/3/2011 1/3/2012 16. DATE COMPLETED: ABANDONED READY TO PRODU									PRODUC	E 🗸		958	ONS (DF,	RKB,	RT, GL):				
18. TOTAL DEPTH:	MD 8,770 19. PLUG BACK T.D.: MD 8,700 20. IF MULTIPLE COMPLETIONS, HO TVD 8,701 TVD 8,631							S, HOW	MANY?*	21. DEI P	PTH B LUG S		MD TVD						
22. TYPE ELECTRIC										23.									
SYNTHETIC COMBO-RSL/SM-CBL/GR/COLLARS/TEMP  WAS WELL CORED? WAS DET RUN? DIRECTIONAL SURVEY?								Υʔ	NO NO NO	<b>✓</b>	YES [ YES [		(Subm	it analysis) it report) it copy)					
24. CASING AND L	NER RECORD	(Report	all string	s set in w	rell)					1					120		Judin	и соруу	
HOLE SIZE	SIZE/GRAI	DE	WEIGHT	(#/ft.)	TOP (	MD)	вотто	M (MD)		EMENTER PTH	CEMENT 1 NO. OF S		SLU VOLUM	RRY E (BBL)	CE	MENT TO	)P **	AMOUNT	PULLED
20"	14" UK	STL	36.		C	0 40 ykn 28					28								
11"		J-55	28		0		2,4				UKD	O 675				0			
7 7/8"	4 1/2"	I-80	11.	6#	0		8,7	44			UKN	1,387			_	990			
																<del></del>		<del> </del>	
						*				·	<u> </u>				┼─			ļ	
25. TUBING RECO	RD				L				<u></u>	· · · · · · · · · · · · · · · · · · ·	L	· · · · · · · · · · · · · · · · · · ·				<del></del>		<u> </u>	·····
SIZE	DEPTH SI	ET (MD)	PACK	ER SET (I	MD)	SIZE		DEPTH	SET (MD)	PACKE	R SET (MD)		SIZE		DEPTH	SET (MI	D)	PACKER S	SET (MD)
2 3/8"	8,19	90				···											$\Box$		
26. PRODUCING IN		700	(445)	T =====				·			RATION RE								
(A) WASATC			(MD) 964		0M (MD) 168	109	(TVD)	вотто	vi (TVD)		L (Top/Bot -		SIZE	NO. HO				ATION STA	TUS
(B) MESAVE			772	<del></del>	620					5,964 6,772		168	0.36	24	-	Open	=-	Squeezed	<u> </u>
(C)		0,	112	- 0,	020					0,772	0.	620	0.36	168	3	Open	=-	Squeezed	<u> </u>
(D)													<del></del>		$\dashv$	Open D	=	Squeezed Squeezed	<u> </u>
28. ACID, FRACTU	RE, TREATME!	NT, CEMI	ENT SQU	EEZE, ET	С.			L	1			L				Open [		oqueezeu	
DEPTH	INTERVAL								AM	DUNT AND T	YPE OF MA	TERIAL							
6772-8620			PUN	/P 7 4	39 BF	SISS	ICK F	12O &		65# 30/			SAND						
					STAG						00 0117	100/1	OAND						
		***		***************************************			<del>/</del>											-	
29. ENCLOSED AT	TACHMENTS:			*****	-		17.0		• • • • • • • • • • • • • • • • • • • •							30.	WELL	STATUS:	<u> </u>
=	RICAL/MECHA			CEMENT	VERIFICA	ATION	_	GEOLOGI CORE AN	C REPOR ALYSIS	=	DST REPOR	RE	DIREC	TIONAL IVE	SURVI	EY	F	PROI	)
									*****			MA	R 2	7 704	^				

DUCTION			IN	TERVAL A (As sho	wn in item #26)				
ODUCED:	TEST DATE: 2/20/201	2	1		TEST PRODUCTION RATES: →	OIL - BBL: GAS - MCF: 1,940		WATER - BBL:	PROD. METHOD: FLOWING
TBG. PRESS. 1,254	CSG. PRESS. 1,806	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF: 1,940	WATER - BBL: 408	INTERVAL STATUS
			IN.	TERVAL B (As sho	wn in item #26)		····		<u> </u>
ODUCED:	TEST DATE:		HOURS TESTE	:D:	TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER BBL:	PROD. METHOD:
TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS - MCF:	WATER – BBL:	INTERVAL STATUS
			IN	TERVAL C (As show	wn in item #26)			<u></u>	<u> </u>
DATE FIRST PRODUCED: TEST DATE:				:D:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS
			IN.	TERVAL D (As sho	wn in Item #26)	<u></u>	<u>!</u>	<u> </u>	<u> </u>
ODUCED:	JCED: TEST DATE;		HOURS TESTE	D:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS MCF:	WATER - BBL:	PROD. METHOD:
TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS
N OF GAS (Sold	, Used for Fuel, V	ented, Etc.)							
nt zones of porosi	ity and contents the	ereof: Cored interva	als and all drill-ster recoveries.	m tests, including de		4. FORMATION	(Log) MARKERS:		
n			Descri	ptions, Contents, etc			Name		Top Measured Depth)
									weasured Depth)
					 	BIRD'S NE MAHOGAN WASATCH	ST NY H		1,161 1,468 1,871 4,344 6,534
	TBG. PRESS.  TBG. PRESS.  TBG. PRESS.  DDUCED:  TBG. PRESS.  DDUCED:  TBG. PRESS.  DDUCED:  TBG. PRESS.	TEST DATE: 2/20/201. TBG. PRESS. 1,254 TBG. PRESS. CSG. PRESS. TBG. PRESS. CSG. PRESS. CSG. PRESS. CSG. PRESS. CDUCED: TEST DATE: TBG. PRESS. CSG. PRESS. CSG. PRESS. CSG. PRESS. CSG. PRESS. CDUCED: TEST DATE: TBG. PRESS. CSG. PRESS. CSG. PRESS.	TEST DATE:  2/20/2012  TBG. PRESS.	TEST DATE:  2/20/2012  TBG. PRESS.  1,254  TBG. PRESS.  1,806  IN  CDUCED:  TEST DATE:  HOURS TESTE  HOURS TESTE  HOURS TESTE  TBG. PRESS.  CSG. PRESS.  API GRAVITY  BTU – GAS  IN  CDUCED:  TEST DATE:  HOURS TESTE  HOURS TESTE  TBG. PRESS.  CSG. PRESS.  API GRAVITY  BTU – GAS  IN  CDUCED:  TEST DATE:  HOURS TESTE  TBG. PRESS.  CSG. PRESS.  API GRAVITY  BTU – GAS  IN  CDUCED:  TEST DATE:  HOURS TESTE  TBG. PRESS.  CSG. PRESS.  API GRAVITY  BTU – GAS  IN  CDUCED:  TEST DATE:  HOURS TESTE  TBG. PRESS.  CSG. PRESS.  API GRAVITY  BTU – GAS  IN  CDUCED:  TEST DATE:  TES	TEST DATE:  2/20/2012  TBG. PRESS.  1,254  TBG. PRESS.  1,806  INTERVAL B (As shore the present of the present	DDUCED: TEST DATE: 2/20/2012	DUCED: TEST DATE: HOURS TESTED: TEST PRODUCTION OIL - BBL: RATES: → O  INTERVAL B (As shown in Item #26)  DUCED: TEST DATE: HOURS TESTED: TEST PRODUCTION OIL - BBL: RATES: → O  INTERVAL B (As shown in Item #26)  TEST DATE: HOURS TESTED: TEST PRODUCTION OIL - BBL: RATES: → O  INTERVAL C (As shown in Item #26)  DUCED: TEST DATE: HOURS TESTED: TEST PRODUCTION OIL - BBL: RATES: → O  INTERVAL C (As shown in Item #26)  DUCED: TEST DATE: HOURS TESTED: TEST PRODUCTION OIL - BBL: RATES: → O  INTERVAL C (As shown in Item #26)  DUCED: TEST DATE: HOURS TESTED: TEST PRODUCTION OIL - BBL: RATES: → OIL - BBL: RAT	DUCED: TEST DATE: 2/20/2012	DDUCED: TEST DATE: HOURS TESTED: TEST PRODUCTION OIL - BBL: GAS - MCF: WATER - BBL: RATES:

The first 210'of the surface hole was drilled with a 12 ¼" bit. The remainder of surface hole was drilled with an 11" bit. DQX csg was run from surface to 4988'; LTC csg was run from 4988' to 8744'.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available rec	
	oras.

NAME (PLEASE PRINT) JAIME SCHARNOWSKE

TITLE REGULATORY ANALYST

SIGNATURE Jain Phoneses

DATE 3/15/2012

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests
- \* ITEM 20: Show the number of completions if production is measured separately from two or more formations.
- \*\* ITEM 24: Cement Top Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to:

Utah Division of Oil, Gas and Mining 1594 West North Temple, Suite 1210

Box 145801

Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

Well: NBU 922-3	36G4BS GREEN						Spud Date: 11/	15/2011		
Project: UTAH-L	JINTAH		Site: NBU	922-36G	3 PAD			Rig Name No: ENSIGN 139/139, PROPETRO 12/12		
Event: DRILLING	G		Start Date	Date: 10/19/2011				End Date: 1/5/2012		
Active Datum: R .evel)	RKB @4,972.00usft (ab	ea	UWI: SV	V/NE/0/9	/S/22/E/36	/0/0/26/PM/N/24	405/E/0/2441/0/0			
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation		
11/15/2011	12:00 - 15:30	3,50	MIRU	01	С	Р		SKID RIG 10' TO NBU 922-36G4BS (WELL 4 OF 4). INSTALL DIVERTOR HEAD AND BOWIE LINE. BUILD DITCH. SPOT IN RIG. SPOT IN CATWALK AND PIPE RACKS. READY. RIG UP PIT PUMP. RIG UP PUMP. PRIME PUMP. INSPECT RIG.		
	15:30 - 16:00	0,50	PRPSPD	01	В	P		HELD PRE-SPUD SAFETY MEETING. TALKED ABOUT COLD WEATHER. P/U 8" 1.83 BEND .17 RPG MUD MOTOR (2ND RUN) (SN 775-77194). M/U QD507 12.25" BIT (2ND RUN) (SN 7014657). TRIP IN TO SPUD.		
	16:00 - 17:30	1.50	DRLSUR	02	D	Р		SPUD 11/15/2011 16:00. DRILL 12.25" HOLE 44'-210' (166', 83'/HR). GPM 400. DH RPM 68 RPM=45, WOB 5-15K. PSI ON/OFF 600/400. UP/DOWN/ ROT 20/20/20 K. DRAG 0 K. CIRC RESERVE W. 8.3# WATER. DRILL DOWN TO 210' W/ 6" COLLARS.		
	17:30 - 20:30	3.00	DRLSUR	06	А	P		TRIP OUT. LAY DOWN 6" DRILL COLLARS, 12 1/4 BIT. CHECK BIT AND MOTOR. PICK UP Q506 11" BIT (3RD RUN) (SN 7024523) SCRIBE MOTOR. P/U 8" DIRECTIONAL ASSEMBLY AND SCRIBE. INSTALL EM TOOL. TRIP IN TO 210' TO DRILL AHEAD.		
	20:30 - 0:00	3.50	DRLSUR	02	D	P		DRILL 11" HOLE ROTATE/SLIDE 210'- 590' (380', 110'/HR). GPM 491. DH RPM 86 RPM=55, WOB 15-20K. PSI ON/OFF 1,007/700. UP/DOWN/ ROT 50/47/49 K. DRAG 1 K. CIRC RESERVE W. 8.3# WATER.		
11/16/2011	0:00 - 4:30	4.50	DRLSUR	02	D	Р		DRILL 11" HOLE ROTATE/SLIDE 590'-1190' (600', 133'/HR). GPM 491. DH RPM 86 RPM=55, WOB 15-20K. PSI ON/OFF 1,145/960. UP/DOWN/ ROT 60/50/55 K. DRAG 5 K. CIRC RESERVE W. 8.3# WATER.		
	4:30 - 12:00	7.50	DRLSUR	02	D	Р		DRILL 11" HOLE ROTATE/SLIDE 1,190'-1,940' (790', 105'/HR). GPM 491. DH RPM 86 RPM=55, WOB 15-20K. PSI ON/OFF 1,545/1,360. UP/DOWN/ ROT 75/56/66 K. DRAG 5 K. CIRC RESERVE W. 8.3# WATER. LOST RETURNS @ 1580' PUT AIR ON THE HOLE @ 1800 CFM		
	12:00 - 15:30	3,50	DRLSUR	02	D	P ,		DRILL 11" HOLE ROTATE/SLIDE 1,940'-2,120' (180', 52'/HR). GPM 491. DH RPM 86 RPM=55, WOB 15-20K. PSI ON/OFF 1,545/1,360. UP/DOWN/ ROT 75/56/66 K. DRAG 9 K. CIRC RESERVE W. 8,3# WATER. HAD SOME COMMUNICATION ISSUES WITH THE PREVIOUSE WELL.		
	15:30 - 19:00	3.50	DRLSUR	06	С	X		WAIT ON CEMENTERS. TRIP OUT OF THE HOLE SO		

WE CAN CEMENT COMMUNICATION.

### **Operation Summary Report**

Well: NBU 922-36G4BS GREEN Spud Date: 11/15/2011 Project: UTAH-UINTAH Site: NBU 922-36G3 PAD Rig Name No: ENSIGN 139/139, PROPETRO 12/12 Event: DRILLING Start Date: 10/19/2011 End Date: 1/5/2012

Active Datum: RKB @4,972.00usft (above Mean Se

Level)

Date

294,972.00usπ (a	bove Mean Se	<b>∋a</b>	OWI: SVV/NE/0/9/S/22/E/36/0/0/26/PM/N/2405/E/0/2441/0/0									
Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From Operation (usft)						
:00 - 0:00	5.00	DRLSUR	23	G	Х	HOLD SAFETY MEETING RIG UP CEMENT CREW.						
						PUMP (100 SX) 20.4 BBLS 15.8# 1.15 YLD 4%						
						CALC DOWN THE BACK SIDE OF THE PREVIOUSE						
						WELL. WAIT 2 HOURS, PUMP (125 SX) 25.6 BBLS						
						15.8# 1.15 YLD 4% CALC DOWN THE BACK SIDE						
						OF THE PREVIOUSE WELL, PUMP (200 SX) 46 BBLS						

	10:00						
	19:00 - 0:00	5.00	DRLSUR	23	G	x	HOLD SAFETY MEETING RIG UP CEMENT CREW, PUMP (100 SX) 20.4 BBLS 15.8# 1.15 YLD 4% CALC DOWN THE BACK SIDE OF THE PREVIOUSE WELL. WAIT 2 HOURS, PUMP (125 SX) 25.6 BBLS 15.8# 1.15 YLD 4% CALC DOWN THE BACK SIDE OF THE PREVIOUSE WELL. PUMP (200 SX) 46 BBLS 15.8# 1.15 YLD 4% CALC DOWN THE BACK SIDE OF THE PREVIOUSE WELL. WAIT 2 HOURS.
11/17/2011	0:00 - 2:00	2.00	DRLSUR	22	G	X	WAIT 2 HOURS, PUMP (125 SX) 25.6 BBLS 15.8# 1.15 YLD 4% CALC DOWN THE BACK SIDE OF THE PREVIOUSE WELL. 2 BBLS OF CEMENT TO SURFACE
1	2:00 - 5:00	3.00	DRLSUR	13	Α	Х	WAIT 3 HOURS FOR CEMENT TO SET UP.
	5:00 - 9:45	4.75	DRLSUR	06	С	Р	PICK UP BOTTOM HOLE ASSEMBLY/DIRECTIONAL TOOLS. TRIP IN TO DRILL AHEAD.
	9:45 - 14:00	4.25	DRLSUR	02	D	Р	DRILL 11" HOLE ROTATE/SLIDE 2,120'-2482' (362', 69'/HR). TD @ 11/17/2011 14:00 GPM 491. DH RPM 86 RPM=55, WOB 15-20K. PSI ON/OFF 1,650/1,440. UP/DOWN/ ROT 84/62/75 K. DRAG 9 K. CIRC RESERVE W. 8.3# WATER. LAST SURVEY 2420' INC-14.31 AZ-75.09 APPROXIMATLY 9' LOW 1.5' LEFT OF THE LINE
	14:00 - 16:00	2.00	DRLSUR	05	Α	Р	CIRCULATE AND CONDITION HOLE FOR CASING RUN.
	16:00 - 20:30	4.50	DRLSUR	06	D	Р	LDDS NO TIGHT WHILE LAYING DOWN DRILL STRING. LAY DOWN DIRECTIONAL TOOLS. PULL MOTOR AND BREAK BIT. LAY DOWN MOTOR.
:	20:30 - 22:00	1.50	DRLSUR	12	Α	Р	MOVE PIPE RACKS AND CATWALK. PULL DIVERTER HEAD. RIG UP TO RUN CSG. AND MOVE CSG INTO POSITION TO P/U.
	22:00 - 0:00	2.00	DRLSUR	12	С	Р	HOLD SAFETY MEETING. RUN 40 JTS OF 8-5/8" 28# J-55 LTC CSG.
11/18/2011	0:00 - 1:30	1.50	DRLSUR	12	С	Р	HOLD SAFETY MEETING. RUN 57 JTS OF 8-5/8" 28# J-55 LTC CSG. LAND FLOAT SHOE @ 2442.44' KB. LAND BAFFLE PLATE @ 2396.44' KB. MADE FLOAT SHOE UP WITH THREAD LOCK. RAN 5 TOTAL CENTRALIZERS.
	1:30 - 2:30	1.00	DRLSUR	12	В	P	HOLD SAFETY MEETING, RUN 200' OF 1". RIG DOWN RIG MOVE OFF WELL, REBUILD DITCH. RIG UP CEMENT TRUCK, 2" HARD LINES, CEMENT HEAD, LOAD PLUG.
	2:30 - 3:30	1.00	DRLSUR	12	E	P	PRESSURE TEST LINES TO 2000 PSI. PUMP 140 BBLS OF WATER AHEAD. CATCH PSI. PUMP 20 BBLS OF 8.3# GEL WATER AHEAD. PUMP (300 SX) 61.4 BBLS OF 15.8# 1.15 YD 5 GAL/SK PREMIUM CEMENT W/ 2% CALC. DROP PLUG ON FLY. DISPLACE W/ 149.5 BBLS OF H20. NO CIRC THROUGH OUT. FINAL LIFT OF 260 PSI AT 4 BBL/MIN. BUMP D. NO CEMENT TO SUBPLACE

3/14/2012

MIN. FLOAT HELD. NO CEMENT TO SURFACE.

#### **Operation Summary Report**

Well: NBU 922-3	6G4BS	GREEN						Spud Date: 11	/15/2011
Project: UTAH-U	INTAH			Site: NBL	922-360	3 PAD			Rig Name No: ENSIGN 139/139, PROPETRO 12/12
Event: DRILLING	}			Start Date	e: 10/19/2	2011		,	End Date: 1/5/2012
Active Datum: RI _evel)	<b @4,9<="" th=""><th>72.00usft (a</th><th>bove Mean S</th><th>ea</th><th>UWI: SV</th><th>N/NE/0/9</th><th>/S/22/E/36</th><th>6/0/0/26/PM/N/24</th><th>405/E/0/2441/0/0</th></b>	72.00usft (a	bove Mean S	ea	UWI: SV	N/NE/0/9	/S/22/E/36	6/0/0/26/PM/N/24	405/E/0/2441/0/0
Date	St	Time art-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	3:30	- 6:30	3.00	DRLSUR	12	E	P		PUMP (150 SX) 30.7 BBLS OF SAME TAIL CEMENT W/ 4% CALC. DOWN BACKSIDE NO CEMENT TO SURFACE. PUMP (50 SX) 10.2 BBLS OF SAME TAIL CEMENT W/ 4% CALC. DOWN BACKSIDE OF PREVIOUSE WELL. PUMP (100 SX) 20.5 BBLS OF SAME TAIL CEMENT W/ 4% CALC. DOWN BACKSIDE OF PREVIOUSE WELL. NO CEMENT TO SURFACE. SHUT DOWN AND CLEAN TRUCK. WAIT 2 HOURS PUMP (225 SX) 46.1 BBLS OF SAME TAIL CEMENT W/ 4% CALC. DOWN BACKSIDE NO CEMENT W/ 4% CALC. SHUT DOWN AND CLEAN TRUCK. WILL TOP OUT AFTER RIG MOVE. RELEASE
12/31/2011	6:00	- 7:00	1.00	MIRU	01	С	Р		RIG @ 11/18/2011 06:30 SKID ON,CENTER OVER WELLHEAD
	7:00	- 8:00	1.00	PRPSPD	14	A	•		NUBOP, FUNCTION TEST BOP
	8:00	- 12:30 - 16:00	4.50	PRPSPD	15	A	P		TEST RAMS,CHOKELINE,MANIFOLD,KILLINE,FLOOR VALVES TO 5K,ANNULAR2.5K,CSG 1500 F/ 30 MIN,INSTALL WEARRING
		- 16:00 - 17:00	3.50	PRPSPD	06	A	P		P/U BHA CRIBE DIR TOOLS, TIH TAG CEMENT@2365
		- 0:00	1.00 7.00	DRLPRO DRLPRO	02 02	F D	P P		DRILL CEMENT & FE F/2365 TO 2492'  DRILL F/2492 TO 3530=1038AVG 148,WOB  18/20,RPM 40/120,GPM 520,PSi 1100/1400,SLIDE
1/1/2012		- 13:00 - 13:30	13.00 0.50	DRLPRO DRLPRO	02 07	D A	P P		18%  DRILL F/3530 TO 5562 =2032 AVG 156 ,WOB  18/20,RPM 40/120,GPM 520,PSI 1200/1600,TORQ  5/8K,SLIDE 120' 6%  RIG SERVICE
	13:30	- 0:00	10.50	DRLPRO	02	D	P		DRILL F/5562 TO 6830 =1268 AVG 121 ,WOB 18/20,RPM 40/120,GPM 520,PSI 1400/1800,TORQ 7/10K,SLIDE 45' 3%'
1/2/2012	0:00	- 1:30	1.50	DRLPRO	02	D	Р		DRILL F/6830 TO 7012 =182 AVG 121 ,WOB 18/20,RPM 40/120,GPM 490,PSI 1700/2100,TORQ 7/10K,SLIDE 0%
	1:30	- 4:00	2.50	DRLPRO	05	G	Р		DISPLACE HOLE WITH 11.2# MUD/STORE WATER,END UP W/MW 9.8/38
	4:00	- 14:30	10.50	DRLPRO	02	D	P		DRILL F/7012 TO 7916 =904 AVG 86 ,WOB 18/20,RPM 40/120,GPM 490,PSI 1700/2100,TORQ 7/10K,SLIDE 77' 7%
		- 15:00	0.50	DRLPRO	07	Α	Р		RIG SERVICE
	15.00	- 0:00	9.00	DRLPRO	02	D	Р		DRILL F/7916 TO 8464 =548 AVG 61 ,WOB 18/20.RPM 40/120,GPM 490,PSI 1900/2300,TORQ 8/11K,SLIDE 0
1/3/2012		- 5:00	5.00	DRLPRO	02	D	Р		DRILL F/8464 TO 6770 =306 AVG 61 ,WOB 18/20,RPM 40/120,GPM 490,PSI 2000/2350,TORQ 10/12K,SLIDE 0
	5:00	- 7:30	2.50	DRLPRO	05	С	Р		FLOW CHECK,FINAL SURVEY@8716'=1.48DEG 127AZI IS 5'NORTH & 4' EAST OF CENTER,CIRCULATE AND,RAISE MW TO 11.5 AROUND,FOR 10 BBL GAIN ON CONN GAS
	7:30	- 13:00	5.50	DRLPRO	06	E	P		SHORTTRIP TO 6200,TIH
		- 16:00 - 0:00	3.00 8.00	DRLPRO	05 06	B A	S P		CIRC BTMS UP., GAS/ UP EARLY 20BBL GAIN,15'FLARE,RAISE MW TO 11.7+ FLOW CHECK OK,PUMP OUT 6 STNDS 80K OVER,PUMPPILL, LDDP TIGHT SPOT 4294

				Opera	ation S	ummai	ary Report
Well: NBU 922-3	36G4BS GREEN						Spud Date: 11/15/2011
Project: UTAH-L	JINTAH		Site: NBI	J 922-360	G3 PAD		Rig Name No: ENSIGN 139/139, PROPETRO 12/12
Event: DRILLING	G		Start Dat	e: 10/19/2	2011		End Date: 1/5/2012
Active Datum: R Level)	ea	UWI: S	UWI: SW/NE/0/9/S/22/E/36/0/0/26/PM/N/2405/E/0/2441/0/0				
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From Operation (usft)
1/4/2012	0:00 - 6:00	6.00	DRLPRO	06	Α	Р	LDDP & DIR TOOLS,BHA#1,
	6:00 - 6:30	0.50	DRLPRO	14	В	Ρ	PULL WEARBUSHING
	6:30 - 16:30 16:30 - 17:30	1.00	DRLPRO	12 05	С	P	SAFETY MT W/ FRANKS,R/U RUN 211JTS 4.5 #11.6 I-80 LTC/DQX CSG TO SHOE DEPTH 8757,FC 8713,MVL MARKER 6476 & WASH TO BTM CIRC BTM UP
	17:30 - 20:00	2.50	DRLPRO	12		P	SAFETY MEET W/ BJ SER,R/U PRESSURE TEST TO 5K,PUMP 25 BBL FRESH,WATER & ,447 SX LEAD @12.1 2.26 YLD- PLII+8%GEL +4%R-3+2%SMS+25#SK CELLOFLAKE+5#SK KOL-SEAL , F/ TAIL 940 SKS # 14.3 - YLD 1.31 YLD 50:50+2%GEL+10%SALT+2%R-3 & ,DISPLACE 135 BBLS,FINAL LIFT PSI ,BUMP PLUG 2500, W/ 500 OVER & FLOATS HELD, 10 BBL WATER BACK TO PIT, 1.5 BBLS WATER BACK TO TRUCK
	20:00 - 0:00	4.00	DDIDDO			_	

Р

WASH OUT STACK & N/D & SET C-22 SLIPS W/ 105K - ROUGH CUT 4.5 CASING & WASH CLEAN

WASH & CLEAN OUT MUD TANKS & RELEASED

RIG @ 06:00 ON 1/5/2012 & R.D.R.T

OUT MUD TANKS

20:00 - 0:00

0:00 - 6:00

1/5/2012

4.00

6.00

DRLPRO

DRLIN1

14

#### 1 General

#### 1.1 Customer Information

Company	US ROCKIES REGION
Representative	
Address	

#### 1.2 Well/Wellbore Information

Well	NBU 922-36G4BS GREEN	Wellbore No.	ОН	
Well Name	NBU 922-36G4BS	Wellbore Name	NBU 922-36G4BS	
Report No.	1	Report Date	1/28/2012	
Project	UTAH-UINTAH	Site	NBU 922-36G3 PAD	
Rig Name/No.		Event	COMPLETION	
Start Date	1/28/2012	End Date	2/15/2012	
Spud Date	11/15/2011	Active Datum	RKB @4,972.00usft (above Mean Sea Level)	
UWI	SW/NE/0/9/S/22/E/36/0/0/26/PM/N/2405/E/0/244	1/0/0	1	

#### 1.3 General

Contractor		Job Method	Supervisor	
Perforated Assembly	PRODUCTION CASING	Conveyed Method		

#### 1.4 Initial Conditions

Fluid Type		Fluid Density	Gross in
Surface Press		Estimate Res Press	No. of In
TVD Fluid Top		Fluid Head	Total She
Hydrostatic Press		Press Difference	Avg Sho
Balance Cond	NEUTRAL		

1.5	Summary
-----	---------

Gross interval	5,964.0 (usft)-8,620.0 (usft	Start Date/Time	2/6/2012	12:00AM	
No. of Intervals	30	End Date/Time	2/6/2012	12:00AM	
Total Shots	192	Net Perforation Interval		50.00	(usft)
Avg Shot Density	3.84 (shot/ft)	Final Surface Pressure			
		Final Press Date			

#### 2 Intervals

#### 2.1 Perforated Interval

Date	Formation/	CCL@	CCL-T	MD Top	MD Base	Shot	Misfires/	Diamete	Carr Type /Carr Manuf	Carr	Phasing	Charge Desc /Charge	Charge	Reason	Misrun
	Reservoir	(usft)	S	(usft)	(usft)	Density	Add. Shot	r r	for the second	Size	(°)	Manufacturer	Weight		
		100	(usft)			(shot/ft)		(in)		(in)			(gram)		
2/6/2012	WASATCH/			5,964.0	5,967.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO	
12:00AM							46.4							N	

#### 2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir		CCL@ (usft)	CCL-T S	MD Top	MD Base (usft)	Shot Density	Misfires/	Diamete	Carr	Type /Carr M	lanuf	Carr Size	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight	Reason	Misrun
	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		(40.5)	(usft)	(40.0)	(4.5.9	(shot/ft)	7144. 01101	(in)				(in)	· ' 1	indiana con ci	(gram)		
2/6/2012 12:00AM	WASATCH/	•			6,165.0	6,168.0	4.00		<del></del>	EXP/		·	3.375	90.00			0 PRODUCTIO N	.1
2/6/2012	MESAVERDE/				6,772.0	6,774.0	3.00		0.360	EXP/			3.375	120.00		23.0	0 PRODUCTIO	
	MESAVERDE/				6,819.0	6,821.0	3.00		0.360	EXP/			3.375	120.00		23.0	N 0 PRODUCTIO	
12:00AM 2/6/2012	MESAVERDE/				6,935.0	6,936.0	3.00		0.360	EXP/			3,375	120.00		23.0	N D PRODUCTIO	
12:00AM																	N	
2/6/2012 12:00AM	MESAVERDE/				6,951.0	6,952.0	3.00		-0.360	EXP/			3.375	120.00		23.0	PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/				7,012.0	7,014.0	3.00		0.360	EXP/			3.375	120.00		23.0	D PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/				7,090.0	7,092.0	4.00		0.360	EXP/			3.375	90.00		23.00	PRODUCTIO N	
	MESAVERDE/				7,218.0	7,219.0	4.00		0.360	EXP/			3.375	90.00	· · · · · · · · · · · · · · · · · · ·	23.00	PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/				7,339.0	7,342.0	4.00		0.360	EXP/			3.375	90.00		23.00	PRODUCTIO N	
	MESAVERDE/				7,527.0	7,530.0	4.00		0.360	EXP/			3.375	90.00		23.00	PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/				7,578.0	7,580.0	4.00		0.360	EXP/			3.375	90.00		23.00	PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/				7,591.0	7,592.0	4.00		0.360	EXP/			3.375	90.00		23.00	PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/				7,650.0	7,652.0	4.00		0.360	EXP/			3.375	90.00	·	23.00	PRODUCTIO N	
The second second	MESAVERDE/				7,687.0	7,688.0	4.00		0.360	EXP/		,-	3.375	90.00		23.00	PRODUCTIO N	
	MESAVERDE/				7,752.0	7,753.0	4.00		0.360	EXP/		*****	3.375	90.00		23.00	PRODUCTIO N	
	MESAVERDE/			-	7,852.0	7,854.0	4.00		0.360	EXP/			3.375	90.00		23.00	PRODUCTIO N	
	MESAVERDE/				7,925.0	7,926.0	4.00		0.360	EXP/			3.375	90.00		23.00	PRODUCTIO N	
	MESAVERDE/				7,968.0	7,970.0	4.00		0.360	EXP/			3.375	90.00		23.00	PRODUCTIO N	
	MESAVERDE/				7,997.0	7,998.0	4.00		0.360	EXP/			3.375	90.00		23.00	PRODUCTIO N	
	MESAVERDE/			14.0	8,127.0	8,128.0	4.00		0.360	EXP/			3.375	90.00		23.00	PRODUCTIO N	
	MESAVERDE/				8,153.0	8,154.0	4.00		0.360	EXP/			3.375	90.00		23.00	PRODUCTIO N	100 No. 1

#### 2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diamete r (in)	Carr Type /Carr Manuf	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
2/6/2012 12:00AM	MESAVERDE/			8,215.0	8,216.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,236.0	8,237.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,261.0	8,262.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,312.0	8,313.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,356.0	8,357.0	4.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,372.0	8,373.0	4.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,564.0	8,568.0	4.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
2/6/2012 12:00AM	MESAVERDE/			8,618.0	8,620.0	4.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	

#### 3 Plots

#### 3.1 Wellbore Schematic



#### **Operation Summary Report**

Well: NBU 922-36G4BS GREEN		Spud Date: 11/15/2011
Project: UTAH-UINTAH	Site: NBU 922-36G3 PAD	Rig Name No: MILES 2/2
Event: COMPLETION	Start Date: 1/28/2012	End Date: 2/15/2012
Active Datum: RKB @4,972.00usft (above I	Mean Sea UWI: SW/NE/0/9/S/22/E/36/0	/0/26/PM/N/2405/E/0/2441/0/0

Active Datum: RKB @4,972.00usft (above Mean Sea

vel)	DOVC IVICAN O		5 Th. 5 Th NE 5/5/5/22/ 250/0/0/20/P (W/N/2405/ 25/0/244 1/0/0								
Date	3 Sept. 10 Sept. 10	Time art-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From Operation (usft)			
1/3/2012	7:30	- 18:00	10.50	COMP	37	В	Р	PSI TEST FRAC VALVES T/7000 PSI. HELD FOR 10 MIN. LOST 0000 PSI. GOOD TEST. BLEED OFF PSI. PERF STG 1)PU 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH PERF AS PER DESIGN. POOH, SWIFN.			
1/28/2012	7:00	- 7:15	0.25	СОМЬ	48		P	HELD SAFETY MEETING : HIGH PRESSURE			
	7:15	- 9:00	1.75	CÓMP	33		P	FILL SURFACE CSG. MIRU B&C QUICK TEST. PSI TEST T/ 1000 PSI. HELD FOR 15 MIN LOST 20 PSI. PSI TEST T/ 3500 PSI. HELD FOR 15 MIN LOST 35 PSI. 1ST PSI TEST T/ 7000 PSI. HELD FOR 30 MIN LOST 83 PSI. NO COMMUNICATION OR MIGRATION WITH SURFACE CSG BLEED OFF PSI. MOVE T/ NEXT WELL. SWIFW			
2/3/2012	7:00	- 18:00	11,00	СОМР	36	В	Р	PSI TEST FRAC VALVES T/ 7000 PSI. HELD FOR 10 MIN. LOST 000 PSI. BLEED OFF PSI. PERF STG 1)PU 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH PERF AS PER DESIGN. POOH, SWIFN.			

### Operation Summary Report

				Opera	tion S	umma	ry Report	
Well: NBU 922-3	6G4BS GREEN			2001 - 11 - 11 - 1 - 1 - 1 - 1 - 1 - 1 -		- Aller	Spud Date: 11/	15/2011
Project: UTAH-U	INTAH		Site: NB	U 922-360	3 PAD			Rig Name No: MILES 2/2
Event: COMPLE	TION		Start Da	te: 1/28/20	12			End Date: 2/15/2012
Active Datum: RI Level)	KB @4,972.00usft (ab	oove Mean Se				/S/22/E/36	6/0/0/26/PM/N/24	
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usff)	Operation
2/7/2012	7:00 - 18:00	11.00	COMP	36	В	P		FRAC STG 1)WHP 490 PSI, BRK 4934 PSI @ 4.7 BPM. ISIP 2263 PSI, FG .70. CALC PERFS OPEN @ 50.4 BPM @ 5484 PSI = 87% HOLES OPEN. ISIP 2699 PSI, FG .75, NPI 436 PSI. MP 6648 PSI, MR 50.9 BPM, AP 4890 PSI, AR 50.6 BPM, PUMPED 30/50 OWATTA SAND. SWI, X-OVER FOR WL.
:								PERF STG 2)PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH SET CBP @ 8403' P/U PERF AS PER DESIGN. POOH, X-OVER FOR FRAC CREW.
								FRAC STG 2)WHP 1060 PSI, BRK 3030 PSI @ 4.4 BPM. ISIP 2259 PSI, FG .71.  CALC PERFS OPEN @ 48 BPM @ 4358 PSI = 100% HOLES OPEN.  ISIP 2459 PSI, FG .74, NPI 200 PSI.  MP 5419 PSI, MR 51 BPM, AP 5044 PSI, AR 50.5 BPM,  PUMPED 30/50 OWATTA SAND. SWI, X-OVER FOR WL.
								PERF STG 3)PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH W/ WL. STACK OUT @ 4985' WORK WL FREE. POOH. REPLACE HAL CBP. REFLUSH WELL BORE. RIH SET CBP @ 8184' P/U PERF AS PER DESIGN. POOH, X-OVER FOR FRAC CREW.
: :								FRAC STG 3)WHP 1200 PSI, BRK 4932 PSI @ 4.8 BPM. ISIP 1820 PSI, FG .67. CALC PERFS OPEN @ 47.6 BPM @ 5096 PSI = 77% HOLES OPEN. ISIP 2459 PSI, FG .74, NPI 639 PSI. MP 6507 PSI, MR 51 BPM, AP 4468 PSI, AR 50.4 BPM, PUMPED 30/50 OWATTA SAND. SWI, X-OVER FOR WL.
								PERF STG 4)PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH SET CBP @ 7884' P/U PERF AS PER DESIGN. POOH, X-OVER FOR FRAC CREW.  FRAC STG 4)WHP 320 PSI, BRK 2359 PSI @ 4.5 BPM. ISIP 1498 PSI, FG .63. CALC PERFS OPEN @ 49.4 BPM @ 4665 PSI = 82% HOLES OPEN. ISIP 1880 PSI, FG .68, NPI 382 PSI. MP 5360 PSI, MR 51 BPM, AP 4655 PSI, AR 50.5 BPM,

1 mg 1 1 mg 1 mg 1 mg 1 mg 1 mg 1 mg 1							ry Report			
	6G4BS GREEN						Spud Date: 11/	15/2011		
Project: UTAH-U	JINTAH 		Site: NBI	J 922-360	33 PAD			Rig Name No: MILES 2/2		
Event: COMPLE	· · · · · · · · · · · · · · · · · · ·			e: 1/28/20	· · · · · · · · · · · · · · · · · · ·	İ	· · · · · · · · · · · · · · · · · · ·	End Date: 2/15/2012		
Active Datum: R Level)	KB @4,972.00usft (a	bove Mean Se	a	UWI: SI	<b>N/NE/0/9</b>	/S/22/E/36	6/0/0/26/PM/N/24	i/E/0/2441/0/0		
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation		
2/8/2012	8:00 - 18:00	10.00	COMP	36	В	Р		HSM. PERF STG 5)PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH SET CBP @ 7622' P/U PERF AS PER DESIGN. POOH, X-OVER FOR FRAC CREW.		
								FRAC STAGE 5) WHP 1507 PSI, BRK 2371 PSI @ 4.5 BPM. ISIP 1757 PSI, FG .67.  CALC PERFS OPEN @ 50.9 BPM @ 3850 PSI = 100% HOLES OPEN.  ISIP 2078 PSI, FG .71, NPI 321 PSI.  MP 4023 PSI, MR 51.4 BPM, AP 3544 PSI, AR 50.9 BPM,		
								PUMPED 30/50 OWATTA SAND  PERF STAGE 6) PU 4 1/2 HAL CBP, & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE, 90 DEG PHASING, SET CBP @ 7372'. P/U & PERF AS PER DES.  FRAC STAGE 6) WHP 454 PSI, BRK 2986 PSI @ 3.7 BPM. ISIP 1286 PSI, FG .62. CALC PERFS OPEN @ 50 BPM @ 4003 PSI = 93% HOLES OPEN.		
								ISIP 2239 PSI, FG .75, NPI 958 PSI. MP 5068 PSI, MR 51.3 BPM, AP 4039 PSI, AR 50.8 BPM, PUMPED 30/50 OWATTA SAND		
								PERF STAGE 7) PU 4 1/2 HAL CBP, & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE, 120 DEG PHASING. SET CBP @ 7044. P/U & PERF AS PER DES.		
								FRAC STAGE 7) WHP 1361 PSI, BRK 2001 PSI @ 3.8 BPM. ISIP 1147 PSI, FG .61.  CALC PERFS OPEN @ 51 BPM @ 4075 PSI = 89% HOLES OPEN.  ISIP 2276 PSI, FG .77, NPI 1129 PSI.  MP 4660 PSI, MR 51.2 BPM, AP 3791 PSI, AR 50.9 BPM,  PUMPED 30/50 OWATTA SAND		
								PERF STAGE 8) PU 4 1/2 HAL CBP, & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE, 90 DEG PHASING. SET CBP @ 6198'. P/U & PERF AS PER DES.		
								FRAC STAGE 8) WHP 163 PSI, BRK 1442 PSI @ 3.5 BPM. ISIP 570 PSI, FG .53. LOW FRAC GRAIDIENT SWIFN.		
								DID NOT PERF OR FRAC STG'S 9 OR 10.		

Vell: NBU 922-3	36G4BS	REEN						Spud Date: 11/	15/2011		
Project: UTAH-L	JINTAH			Site: NBL	J 922-360	G3 PAD			Rig Name No: MILES 2/2		
vent: COMPLE	TION			Start Date	e <sup>.</sup> 1/28/20	012			End Date: 2/15/2012		
ctive Datum: R	KB @4,9	72.00usft (a	bove Mean Se				/22/E/36/0	/0/26/PM/N/24	405/E/0/2441/0/0		
evel)		`							3.2.3.2.11110.0		
Date	Sta	Γime art-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation		
2/9/2012	8:00	- 10:00	2.00	COMP	34	I	Р		OPEN WELL 530 PSI. FLUSH CSG. PU 4 1/2 8K HAL CBP. RIH SET CBP @ 5888'. POOH. DONE FRACING THIS WELL.		
									STG 8 IS PERFED BUT NOT FRACED DUE T/ LOW FG53.		
									STG 9 & 10 DID NOT PERF OR FRAC.		
2/15/2012	7:00	- 7:30	0.50	COMP	48		P		TOTAL SAND = 143,965 LBS TOTAL CLFL = 7439 BBLS MILL PLUGS		
	7:30	- 18:00	10.50	COMP	44		P		MIRU, NDWH, NU BOP'S, TEST BOP'S, PU BIT, BIT SUB, SEATING NIPPLE, POBS, TBG, TIH TO PLUG# 1, 5888', MILL 8 PLUGS, CLEAN OUT 20' TO 8699' PBTD, PU TO 8190.43', LAND TBG, ND BOP'S, NUWH, POBS, 2000# TURN TO FBC, RDMO		
									PLUG# 1 5888' 0' SAND 5 MIN 0# KICK PLUG# 2 6198' 20' SAND 5 MIN 300# KICK PLUG# 3 7044' 30' SAND 5 MIN 200# KICK PLUG# 4 7378' 20' SAND 5 MIN 400# KICK PLUG# 5 7622' 20' SAND 5 MIN 400# KICK PLUG# 6 7884' 30' SAND 5 MIN 200# KICK PLUG3 7 8184' 30' SAND 7 MIN 500# KICK PLUG# 8 8403' 30' SAND 5 MIN 400# KICK		
									PBTD 8699" BTM PERF 8620'		
									TBG 258 JTS 8173.40' KB 15.00' HANGER .83' XNSN 1.875" 2.20' EOT 8190.43'		
	17:15	_		PROD	50				FRAC WTR 7,439 BBLS RCVD 2,100 BBLS LTR 5,339 BBLS		
					30				WELL TURNED TO SALES @ 1715 HR ON 2/15/2012 - 1900 MCFD, 1920 BWPD, FCP 2800#, FTP 2000#, 20/64 CK		
2/18/2012	7:00	-		PROD	50				WELL IP'D ON 2/18/12 - 1823 MCFD, 0 BOPD, 408 BWPD, CP 1972#, FTP 1301#, CK 20/64", LP 131#,		



Project: Uintah County, UT UTM12 Site: NBU 922-36G3 PAD Well: NBU 922-36G4BS

Wellbore: OH Design: OH





WELL DETAILS: NBU 922-36G4BS


GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

+N/-S +E/-W Northing Easting Latittude Longitude
0.00 0.00 14527658.24 2092227.28 39° 59' 35.538 N 109° 23' 12.926 W









#### PROJECT DETAILS: Uintah County, UT UTM12

Geodetic System: Universal Transverse Mercator (US Survey Feet)
Datum: NAD 1927 - Western US
Ellipsodi: Clarke 1866
Zone: Zone 12N (114 W to 108 W)
Location: SECTION 36 T9S R22E
System Datum: Mean Sea Level

Design: OH (NBU 922-36G4BS/OH)

Created By: RobertScott Date: 13:35, January 16 2012



# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-36G3 PAD NBU 922-36G4BS

OH

Design: OH

## **Standard Survey Report**

16 January, 2012







Company:

Kerr McGee Oil and Gas Onshore LP

Project: Site:

Uintah County, UT UTM12 NBU 922-36G3 PAD

Well:

NBU 922-36G4BS

Wellbore: Design:

OH

Local Co-ordinate Reference:

TVD Reference: **MD Reference:** 

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139) GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

North Reference: True

**Survey Calculation Method:** 

Database:

Minimum Curvature

Well NBU 922-36G4BS

EDM 5000.1 Single User Db

Project

Uintah County, UT UTM12

Map System: Geo Datum:

Universal Transverse Mercator (US Survey Feet)

NAD 1927 - Western US

Map Zone:

Zone 12N (114 W to 108 W)

System Datum:

Mean Sea Level

Site

From:

NBU 922-36G3 PAD, SECTION 36 T9S R22E

Site Position:

Lat/Long

Northing:

14,527,629.00 usft

Latitude: Longitude:

39° 59' 35.250 N

Position Uncertainty:

0.00 ft

Easting: Slot Radius: 2,092,221.64 usft

109° 23' 13.006 W

13.200 in

**Grid Convergence:** 

1.04 °

Well Well Position

+N/-S +E/-W

OH

0.00 ft

Northing:

14,527,658.25 usft

Latitude:

39° 59' 35.538 N

Position Uncertainty

0.00 ft 0.00 ft

NBU 922-36G4BS, 2435 FNL 2447 FEL

Easting:

2,092,227.28 usft

Longitude:

109° 23' 12.926 W

Wellhead Elevation:

ft

Ground Level:

4,958.00 ft

Wellbore

Magnetics

**Model Name** 

Sample Date

Declination (°)

Dip Angle (°)

Field Strength

72.15

(nT)

IGRF2010

02/09/11

0.00

11.07

65.89

52,375

Design

Audit Notes:

Version:

1.0

ОН

Phase:

ACTUAL

Tie On Depth:

0.00

0.00

**Vertical Section:** 

Depth From (TVD)

(ft)

+N/-S (ft)

0.00

+E/-W (ft)

Direction

(°)

Survey Program

(ft)

01/16/12 Date

From

To (ft)

Survey (Wellbore)

Tool Name

Description

10.00 2,575.00 2,430.00 Survey #1 SDI MWD SURFACE (OH) 8,770.00 Survey #2 SDI MWD PRODUCTION (OH)

MWD SDI MWD SDI

MWD - Standard ver 1.0.1 MWD - Standard ver 1.0.1

Survey

Measured Depth (ft)	inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
10.00	0.00	0.00	10.00	0.00	0.00	0.00	0.00	0.00	0.00
191.00	0.37	87.39	191.00	0.03	0.58	0.56	0.20	0.20	0.00
FIRST SDI M	IWD SURFACE S	SURVEY							
276.00	1.41	63,49	275.99	0.51	1.79	1.86	1.27	1.22	-28.12
360.00	3.56	73.94	359.90	1.69	5.23	5.49	2.61	2.56	12.44
450.00	4.91	76.38	449.66	3.37	11.65	12.13	1.51	1.50	2.71
540.00	6.77	75.68	539.19	5.59	20.54	21.26	2.07	2.07	-0.78
630.00	8.34	68.68	628.40	9.27	31.76	33.07	2.02	1.74	-7.78
720.00	10.17	67.81	717.23	14.65	45.20	47.51	2.04	2.03	-0.97





Company:

Kerr McGee Oil and Gas Onshore LP

Project:

Uintah County, UT UTM12

Site: Well: NBU 922-36G3 PAD NBU 922-36G4BS

Wellbore: Design: OH OH Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

Survey Calculation Method: Database: Well NBU 922-36G4BS

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139) True

Minimum Curvature

EDM 5000.1 Single User Db

/ey	15(A) - 1 - 10 - 10 / 10 / 10 / 10 / 10 / 10	75-7728-712-7513	- Section of the sect	The state of the s	and the second of the second o		The following services of the		and the second of the second o
Measured Depth			Vertical			Vertical	Dogleg	Build	Tuen
υ <del>σ</del> ριπ (ft)	Inclination (°)	Azimuth (°)	Depth (ft)	+N/-S (ft)	+E/-W	Section (ft)	Rate (%100ft)	Rate	Rate
73424440735	Manay Salasan	"国际"的"国际"。		119	(ft)		(710011)	(°/100ft)	(°/100ft)
810.00	10.99	69.93	805.70	20.59	60.61	64.01	1.01	0.91	2.36
900.00	12.07	70.23	893.88	26.72	77.53	81.99	1.20	1.20	0.33
990.00	12.54	69.99	981.81	33.25	95.56	101.15	0.53	0.52	-0.27
1,080.00	12.61	72.03	1,069.65	39.62	114.09	120.74	0.50	0.08	2.27
1,170.00	12.88	72.73	1,157.44	45.63	133.01	140.60	0.35	0.30	0.78
1,260.00	13.20	72.96	1,245.12	51.62	152.42	160.90	0.36	0.36	0.26
1,350.00	13.30	72.94	1,332.72	57.67	172.14	181.53	0.11	0.11	-0.02
1,440.00	13.38	72.42	1,420.29	63.85	191.96	202.29	0.16	0.09	-0.58
1,530.00	12.66	71.66	1,507.98	70.10	211.25	222.57	0.82	-0.80	-0.36 -0.84
1,620.00	13.71	70.75	1,595.60	76.72	230.68	243.09	1.19	1.17	-0.64 -1.01
1,710.00	15.07	72.16	1,682.78	83.82	251.89	265.45	1.56	1.17	1.57
4 000 00	4454	70 70	4 700 70						
1,800.00 1,890.00	14.54	72.78	1,769.79	90.75	273.82	288.45	0.61	-0.59	0.69
1,980.00	15.14	74.91	1,856.79	97.15	295.96	311.49	0.90	0.67	2.37
	15.41 15.55	73.60	1,943.61	103.59	318.77	335.18	0.49	0.30	-1. <b>4</b> 6
2,070.00	15.55 15.66	72.93	2,030.34	110.50	341.78	359.20	0.25	0.16	-0.74
2,160.00	15.66	72.78	2,117.03	117.64	364.91	383.41	0.13	0.12	-0.17
2,250.00	14.97	71.03	2,203.83	125.02	387.51	407.17	0.92	-0.77	-1.94
2,340.00	14.57	71.87	2,290.86	132.32	409.26	430.12	0.50	-0.44	0.93
2,430.00	14.31	75.09	2,378.01	138.70	430.77	452.55	0.94	-0.29	3.58
LAST SDI M	WD SURFACE S	URVEY							
2,575.00	13.38	70.32	2,518.80	148.96	463.88	487.21	1.01	-0.64	-3.29
FIRST SDI N	IWD PRODUCTI	ON SURVEY							
2,612.00	12.38	69.60	2,554.87	151.79	471.63	495.45	2.74	-2.70	-1.95
2,702.00	11.21	74.89	2,642.97	157.43	489.12	513.83	1.77	-1.30	5.88
2,793.00	9.96	76.10	2,732.42	161.63	505.30	530.52	1.40	-1.37	1.33
2,883.00	10.07	73.58	2,821.05	165.72	520.40	546.15	0.50	0.12	-2.80
2,974.00	10.09	77.99	2,910.65	169.63	535.83	562.03	0.85	0.02	4.85
3,064.00	9.09	78. <b>85</b>	2,999.39	172.65	550.52	576.94	1.12	-1.11	0.96
3,155.00	7.33	72.90	3,089.46	175.74	563.12	589.88	2.15	-1.93	-6.54
3,245.00	7.78	68.20	3,178.68	179.69	574.26	601.70	0.85	0.50	-5.22
3,336.00	6.60	69.11	3,268.96	183.85	584.87	613.07	1.30	-1.30	1.00
3,426.00	5.24	72.79	3,358.48	186.91	593.63	622.34	1.57	-1.50 -1.51	4.09
3,517.00	4.26	74.84	3,449.16	189.02	600.86	629.87	1.09	-1.08	2.25
3,608.00	2.19	92.48	3,540.02	189.83	gne on	F0.4.00			
3,698.00	0.95	94.91	3,629.98		605.86	634.88	2.50	-2.27	19.38
3,789.00	0.95	259.15		189.69	608.32	637.18	1.38	-1.38	2.70
3,879.00	0.51	259.15 314.20	3,720.98	189.55	608.67	637.48	1.59	-0.48	180.48
3,969.00	0.56		3,810.97	189.76	607.98	636.88	0.53	0.02	61.17
3,505.00	0.56	226.91	3,900.97	189.75	607.36	636.29	0.84	0.03	-96.99
4,060.00	0.34	201.80	3,991.97	189.20	606.94	635.71	0.32	-0.24	-27.59
4,150.00	1.05	170.06	4,081.96	188.14	606.98	635.43	0.87	0.79	-35.27
4,241.00	1.51	172.59	4,172.94	186.13	607.28	635.10	0.51	0.51	2.78
4,332.00	0.64	166.26	4,263.92	184.45	607.55	634.85	0.96	-0.96	-6.96
4,422.00	0.71	258.42	4,353.92	183.85	607.13	634.26	1.08	0.08	102.40





Company:

Kerr McGee Oil and Gas Onshore LP

Project: Site: Uintah County, UT UTM12 NBU 922-36G3 PAD

Well:

NBU 922-36G4BS

Wellbore: Design: OH OH Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

Survey Calculation Method:

Database:

Well NBU 922-36G4BS

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139) GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

True

Minimum Curvature

EDM 5000.1 Single User Db

Sigil.	the transfer of processing and the second	A SHAN ALLESS AND		Database:			EDM 5000.1 Sir	igle User Db	
rvey		eri museli ili digil. CVASTI Albusi We	<del>vivedina vika bu</del> divenima a final				radio de la gracia de la compansión de la Compansión de la compansión		A CONTRACTOR OF THE STATE OF TH
Measured Depth	Inclination	Azimuth	Vertical Depth	+N/-S	+E/-W	Vertical Section	Dogleg Rate	Build Rate	Turn Rate
<b>(ft)</b>	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)
4,513.00	0.75	238.22	4,444.91	183,42	606.07	633.12	0.28	0.04	-22.20
4,603.00	0.84	228.06	4,534.90	182.67	605.08	631.94	0.19	0.10	-22.20 -11.29
4,694.00	0.53	211.35	4,625.90	181.86	604.36	631.02	0.40	-0.34	-18.36
4,784.00	0.70	200.63	4,715.89	180.99	603.95	630.36	0.23	0.19	-11.91
4,875.00	1.37	194.50	4,806.87	179.42	603.48	629.43	0.75	0.74	-6.74
4,965.00	0.30	135.01	4,896.86	178.21	603.38	628.96	1.38	-1.19	-66.10
5,056.00	1.32	49.90	4,987.86	178.72	604.35	630.04	1.46	1.12	-93.53
5,146.00	1.49	51.67	5,077.83	180.11	606.06	632.10	0.19	0.19	1.97
5,237.00	0.85	69.14	5,168.81	181.08	607.62	633.88	0.80	-0.70	19.20
5,327.00	1.24	76.77	5,258.79	181.55	609.19	635.52	0.46	0.43	8.48
5,418.00	1.33	103.56	5,349.77	181.52	611.18	637.40	0.66	0.10	29.44
5,508.00	1.31	102.84	5,439.75	181.05	613.20	639.17	0.03	-0.02	-0.80
5,599.00	1.06	123.55	5,530.73	180.35	614.91	640.59	0.54	-0.02	22.76
5,689.00	1.47	133,51	5,620.71	179.10	616.44	641.67	0.52	0.46	
5,780.00	0.26	80.22	5,711.70	178.33	617.49	642.43	1.46	-1.33	11.07 -58.56
5,870.00	0.47	345.93	5,801.70	178.72	617.60	640.00	0.00		
5,961.00	0.65	344.25	5,892.69	179.58	617.60	642.66	0.62	0.23	-104.77
6,051.00	0.83	338.74	5,982.68	179.56	617.37	642.70	0.20	0.20	-1.85
6,142.00	0.43	350.94	6,073.68	181.63	617.00	642.68	0.21	0.20	-6.12
6,232.00	0.09	348.55	6,163.68	182.03	616.71 616.64	642.69 642.75	0.46 0.38	-0.44 -0.38	13.41 -2.66
6,323.00	0.70	220.07	0.054.07					3.55	-2.00
6,413.00	0.79	338.97	6,254.67	182.69	616.40	642.73	0.77	0.77	-10.53
•	1.04	346.20	6,344.66	184.06	615.98	642.75	0.31	0.28	8.03
6,504.00	0.77	333.12	6,435.65	185.41	615.51	642.71	0.37	-0.30	-14.37
6,594.00	0.35	357.34	6,525.65	186.22	615.22	642.69	0.53	-0.47	26.91
6,685.00	0.67	8.25	6,616.64	187.03	615.29	643.00	0.37	0.35	11.99
6,775.00	0.32	95.46	6,706.64	187.52	615.61	643.46	0.81	-0.39	96.90
6,866.00	0.59	135.91	6,797.64	187.16	616.19	643.90	0.44	0.30	44.45
6,956.00	0.71	154.79	6,887.63	186.33	616.75	644.18	0.27	0.13	20.98
7,047.00	0.89	139.59	6,978.62	185.28	617.45	644.52	0.30	0.20	-16.70
7,138.00	1.55	169.88	7, <b>06</b> 9.60	183.53	618.12	644.62	0.99	0.73	33.29
7,228.00	0.47	231,29	7,159.59	182.10	618.05	644.12	1.54	-1.20	68.23
7,319.00	0.53	198.08	7,250.59	181. <del>4</del> 7	617.63	643.52	0.32	0.07	-36.49
7,409.00	0.69	172.03	7,340.58	180.53	617.57	643.18	0.35	0.18	-28.94
7,500.00	1.06	181.29	7,431.57	179.15	617.63	642.81	0.43	0.41	10.18
7,590.00	0.50	232.20	7,521.56	178.08	617.30	642.17	0.93	-0.62	56.57
7,680.00	0.95	319.44	7,611.56	178.40	616.51	641.51	1.17	0.50	96.93
7,771.00	0.71	326.22	7,702.55	179.44	615.70	641.07	0.28	-0.26	7.45
7,862.00	0.44	332.11	7,793.54	180.22	615.22	640.85	0.30	-0.30	6.47
7,952.00	0.32	111.75	7,883.54	180.43	615.30	640.99	0.79	-0.13	155.16
8,042.00	0.51	74.01	7,973.54	180.45	615.91	641.58	0.36	0.21	-41.93
8,133.00	0.74	80.39	8,064.53	180.66	616.88	642.57	0.26	0.25	7.01
8,224.00	1.06	133.48	8,155.52	180.18	618.07	643.55	0.26	0.25	
8,314.00	1.11	145.72	8,245.51	178.89	619.17	644.20	0.94	0.35	58.34
8,405.00	1.38	140.49	8,336.49	177.31	620.36	644.85	0.26	0.30	13.60 -5.75





Turn

Company:

Project:

Uintah County, UT UTM12

Site:

NBU 922-36G3 PAD NBU 922-36G4BS

Well: Wellbore: Design:

αн

Kerr McGee Oil and Gas Onshore LP

Local Co-ordinate Reference:

Well NBU 922-36G4BS

TVD Reference:

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

Build

MD Reference:

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

North Reference:

Database:

True

Survey Calculation Method:

Minimum Curvature

ОН

EDM 5000.1 Single User Db

	The second second	The state of the state of		100000000000000000000000000000000000000	T. T	The state of the s
Survey						
ouivey	Allega de la companya della companya della companya de la companya de la companya della companya					
		これ アイドー はか しゅかっか			Annual Control of the	
	and the first of the second of the					
			Manager 1987年 -	A Section Control of the Control of the	and the second of the second of the second	
Measured			Vertical			familiant Same
	A. Laure 1970 and the 1994		vernen		right of the State of the	/ertical Dogleg
Depth					一种人名英格兰人姓氏克特的	
Depin	Inclination	Azimuth	Depth	+N/-S	+E/-W \$	section Rate
				· · · · · · · · · · · · · · · · · · ·	- M-44	ACCUOIT IVALE
(ft)	<b>/</b> 0\	(0)	1445		The second residual and the SA	
		(*)	(ft)	/At )	/41\	/#\ /9/4.00#\

Rate Rate (°/100ft) (°/100ft) 8,495.00 1.43 130.45 8,426.46 175.75 621.91 645.84 0.28 0.06 -11.16 8,586.00 1.06 143.94 8,517.44 174.33 623.27 646.70 0.52 -0.41 14.82 8,676.00 1.49 135.59 8,607.42 172.82 624.57 647.48 0.52 0.48 -9.28 8,716.00 1.48 127.33 8,647.40 172.14 625.35 648.01 0.54 -0.03 -20.65 LAST SDI MWD PRODUCTION SURVEY 8,770.00 1.48 127.33 8,701.38 171.29 626.46 648.81 0.00 0.00 0.00

**SDI PROJECTION TO BIT** 

Design Annotations				
Measured Depth (ff)	Vertical Depth (ft)	Local Coord +N/-S (ft)	inates +E/-W (ft)	Comment
191.00	191.00	0.03	0.58	FIRST SDI MWD SURFACE SURVEY
2,430.00	2,378.01	138.70	430.77	LAST SDI MWD SURFACE SURVEY
2,575.00	2,518.80	148.96	463.88	FIRST SDI MWD PRODUCTION SURVEY
8,716.00	8,647.40	172.14	625.35	LAST SDI MWD PRODUCTION SURVEY
8,770.00	8,701.38	171.29	626.46	SDI PROJECTION TO BIT

Checked By:	A 1 D		
Checked by.	Approved By:	Date	<b>z</b> .
			<b>,</b>



# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-36G3 PAD NBU 922-36G4BS

OH

Design: OH

## **Survey Report - Geographic**

16 January, 2012





#### SDI

Survey Report - Geographic



Company:

Kerr McGee Oil and Gas Onshore LP

Project:

Uintah County, UT UTM12

Site: Well: NBU 922-36G3 PAD

Wellbore:

NBU 922-36G4BS

Design:

OH OH Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference: Survey Calculation Method:

Database:

Well NBU 922-36G4BS

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139) GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

True

Minimum Curvature

EDM 5000.1 Single User Db

Project

Uintah County, UT UTM12

Map System: Geo Datum:

Universal Transverse Mercator (US Survey Feet)

NAD 1927 - Western US

Map Zone:

Zone 12N (114 W to 108 W)

System Datum:

Mean Sea Level

Site

NBU 922-36G3 PAD, SECTION 36 T9S R22E

Site Position: From:

Lat/Long

Northing: Easting:

14,527,629.00 usft 2,092,221.64 usft

Latitude:

39° 59' 35.250 N

**Position Uncertainty:** 

Slot Radius:

Longitude:

109° 23' 13.006 W

0.00 ft

13.200 in

Grid Convergence:

1.04°

Well Well Position NBU 922-36G4BS, 2435 FNL 2447 FEL

0.00 ft

0.00 ft

Northing: Easting:

14,527,658.25 usft

Latitude: Longitude: 39° 59' 35.538 N

**Position Uncertainty** 

0.00 ft

Wellhead Elevation:

2,092,227.28 usft ft

Ground Level:

109° 23' 12.926 W 4,958.00 ft

Wellbore

OH

+N/-S

+E/-W

Magnetics

**Model Name** 

Sample Date

Declination

(°)

Dip Angle (°)

Field Strength

(nT)

72.15

IGRF2010

02/09/11

0.00

11.07

65.89

52,375

Design

Audit Notes:

Version:

1.0

OH

Phase:

(ft)

ACTUAL

Tie On Depth:

0.00

Vertical Section:

Depth From (TVD)

+NV-S (ft)

0.00

+E/-W

0.00

Direction

(°)

Survey Program

Date 01/16/12

From (ft)

То (ft)

Survey (Wellbore)

**Tool Name** 

Description

10.00 2,575.00 2,430.00 Survey #1 SDI MWD SURFACE (OH)

MWD SDI

MWD - Standard ver 1.0.1

8,770.00 Survey #2 SDI MWD PRODUCTION (OH)

MWD SDI

MWD - Standard ver 1.0.1

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	14,527,658.25	2,092,227.28	39° 59′ 35.538 N	109° 23' 12.926 \
10.00	0.00	0.00	10.00	0.00	0.00	14,527,658.25	2,092,227.28	39° 59′ 35.538 N	109° 23' 12.926 '
191.00	0.37	87.39	191.00	0.03	0.58	14,527,658.28	2,092,227.86	39° 59′ 35.538 N	109° 23' 12.919
FIRST SI	DI MWD SURF	ACE SURVE	Υ						
276.00	1.41	63.49	275.99	0.51	1.79	14,527,658.79	2,092,229,06	39° 59′ 35.543 N	109° 23' 12.903
360.00	3.56	73.94	359.90	1.69	5.23	14,527,660.03	2,092,232.47	39° 59′ 35.555 N	109° 23' 12.859
450.00	4.91	76.38	449,66	3.37	11.65	14,527,661.83	2,092,238.87	39° 59′ 35.571 N	109° 23' 12.777
540.00	6.77	75.68	539.19	5.59	20.54	14,527,664.21	2,092,247.71	39° 59′ 35.593 N	109° 23' 12.662
630.00	8.34	68.68	628.40	9.27	31.76	14,527,668.09	2,092,258.86	39° 59' 35.630 N	109° 23' 12.518
720.00	10.17	67.81	717.23	14.65	45.20	14,527,673.71	2,092,272.20	39° 59' 35.683 N	109° 23' 12.346
810.00	10.99	69.93	805.70	20.59	60.61	14,527,679,93	2.092.287.51	39° 59′ 35.742 N	109° 23' 12 148



#### SDI

Survey Report - Geographic



Company:

Kerr McGee Oil and Gas Onshore LP

Project: Site: Uintah County, UT UTM12 NBU 922-36G3 PAD

Well:

NBU 922-36G4BS

Wellbore: Design: OH OH Local Co-ordinate Reference:

TVD Reference:

e: Well NBU 922-36G4BS GL 4958' & KB 14' @ 49

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139) GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

MD Reference: North Reference:

True

Survey Calculation Method:

Database:

Minimum Curvature
EDM 5000.1 Single User Db

Measured		그들은 사이에게 걸	ا - د العدد ا	Pilipier Marks			이 사람들은 그리다 나를 다	유명이 얼마 하지 않아요 나를 받는다	
measured Depth	Inclination	Azimuth	Vertical Depth	+N/-S	+E/-W	Map Northing	Map Easting		
(ft)	(°)	<b>(°</b> )	(ft)	(ft)	(ft)	(usft)	(usft)	Latitude	Longitude
900.00	12.07	70.23	893.88	26.72	77.53	14,527,686.37	2,092,304.31	39° 59′ 35.802 N	109° 23' 11.93
990.00	12.54	69.99	981.81	33.25	95.56	14,527,693.22	2,092,322.22	39° 59′ 35.867 N	109° 23' 11.69
1,080.00	12.61	72.03	1,069.65	39.62	114.09	14,527,699.93	2,092,340.63	39° 59' 35.930 N	109° 23' 11.46
1,170.00	12.88	72.73	1,157.44	45.63	133.01	14,527,706.28	2,092,359.44	39° 59′ 35.989 N	109° 23' 11.21
1,260.00	13.20	72.96	1,245.12	51.62	152.42	14,527,712.62	2,092,378.73	39° 59' 36.048 N	109° 23' 10.96
1,350.00	13.30	72.94	1,332.72	57.67	172.14	14,527,719.02	2,092,398.34	39° 59′ 36.108 N	109° 23' 10.71
1,440.00	13.38	72.42	1,420.29	63.85	191.96	14,527,725.56	2,092,418.05	39° 59′ 36,169 N	109° 23' 10.46
1,530.00	12.66	71.66	1,507.98	70.10	211.25	14,527,732.16	2,092,437.22	39° 59' 36.231 N	109° 23' 10.21
1,620.00	13.71	70.75	1,595.60	76.72	230.68	14,527,739.13	2,092,456.53	39° 59' 36.296 N	109° 23' 9.96
1,710.00	15.07	72.16	1,682.78	83.82	251.89	14,527,746.61	2,092,477.61	39° 59' 36.366 N	109° 23' 9.69
1,800.00	14.54	72.78	1,769.79	90.75	273.82	14,527,753.93	2,092,499.41	39° 59′ 36.435 N	109° 23' 9.40
1,890.00	15.14	74.91	1,856.79	97.15	295.96	14,527,760.74	2,092,521.43	39° 59' 36,498 N	109° 23' 9.12
1,980.00	15.41	73.60	1,943.61	103.59	318.77	14,527,767.59	2,092,544.12	39° 59' 36.562 N	109° 23' 8.83
2,070.00	15.55	72.93	2,030.34	110.50	341.78	14,527,774.92	2,092,567.00	39° 59' 36.630 N	109° 23' 8.53
2,160.00	15.66	72.78	2,117.03	117.64	364.91	14,527,782.47	2,092,590.00	39° 59′ 36.701 N	109° 23' 8.23
2,250.00	14.97	71.03	2,203.83	125.02	387.51	14,527,790.26	2,092,612.46	39° 59′ 36.774 N	109° 23' 7,94
2,340.00	14.57	71.87	2,290.86	132.32	409.26	14,527,797.95	2,092,634.07	39° 59′ 36.846 N	109° 23' 7.66
2,430.00	14.31	75.09	2,378.01	138.70	430.77	14,527,804.72	2,092,655.46	39° 59′ 36.909 N	109° 23' 7.39
LAST SE	MWD SURF	ACE SURVEY	ŕ						
2,575.00	13.38	70.32	2,518.80	148.96	463.88	14,527,815.58	2,092,688.39	39° 59′ 37.010 N	109° 23' 6.96
FIRST SI	DI MWD PROD	DUCTION SU	RVEY						
2,612.00	12.38	69.60	2,554.87	151.79	471.63	14,527,818.55	2,092,696.08	39° 59′ 37.038 N	109° 23' 6.86
2,702.00	11.21	74.89	2,642.97	157.43	489.12	14,527,824.50	2,092,713.47	39° 59′ 37.094 N	109° 23' 6.64
2,793.00	9.96	76.10	2,732.42	161.63	505.30	14,527,828.99	2,092,729.57	39° 59' 37.136 N	109° 23' 6.43
2,883.00	10.07	73.58	2,821.05	165.72	520.40	14,527,833.36	2,092,744.59	39° 59′ 37.176 N	109° 23' 6.23
2,974.00	10.09	77.99	2,910.65	169.63	535.83	14,527,837.55	2,092,759.95	39° 59′ 37,215 N	109° 23' 6.04
3,064.00	9.09	78.85	2,999.39	172.65	550.52	14,527,840.83	2,092,774.58	39° 59′ 37.244 N	109° 23' 5.85
3,155.00	7.33	72.90	3,089.46	175.74	563.12	14,527,844.15	2,092,787.12	39° 59' 37.275 N	109° 23' 5.69
3,245.00	7.78	68.20	3,178.68	179.69	574.26	14,527,848.30	2,092,798.19	39° 59′ 37.314 N	109° 23' 5.54
3,336.00	6.60	69.11	3,268.96	183.85	584.87	14,527,852.65	2,092,808.72	39° 59′ 37.355 N	109° 23' 5.41
3,426.00	5.24	72.79	3,358.48	186.91	593.63	14,527,855.87	2,092,817.42	39° 59' 37.385 N	109° 23' 5.29
3,517.00	4.26	74.84	3,449.16	189.02	600.86	14,527,858.11	2,092,824.62	39° 59' 37.406 N	109° 23' 5.20
3,608.00	2.19	92.48	3,540.02	189.83	605.86	14,527,859.01	2,092,829.60	39° 59′ 37.414 N	109° 23' 5.14
3,698.00	0.95	94.91	3,629.98	189.69	608.32	14,527,858.91	2,092,832.06	39° 59′ 37.413 N	109° 23' 5.10
3,789.00	0.51	259.15	3,720.98	189.55	608.67	14,527,858.78	2,092,832.42	39° 59′ 37.411 N	109° 23' 5.10
3,879.00	0.53	314.20	3,810.97	189.76	607.98	14,527,858.98	2,092,831.72	39° 59′ 37.414 N	109° 23' 5.11
3,969.00	0.56	226.91	3,900.97	189.75	607.36	14,527,858.96	2,092,831.10	39° 59′ 37.413 N	109° 23' 5.12
4,060.00	0.34	201.80	3,991.97	189.20	606.94	14,527,858.40	2,092,830.69	39° 59′ 37.408 N	109° 23′ 5.12
4,150.00	1.05	170.06	4,081.96	188.14	606.98	14,527,857.34	2,092,830.75	39° 59′ 37.398 N	109° 23' 5.12
4,241.00	1.51	172.59	4,172.94	186.13	607.28	14,527,855.33	2,092,831.09	39° 59′ 37.378 N	109° 23' 5.12
4,332.00	0.64	166.26	4,263.92	184.45	607.55	14,527,853.66	2,092,831.39	39° 59′ 37.361 N	109° 23' 5.11
4,422.00	0.71	258.42	4,353.92	183.85	607.13	14,527,853.05	2,092,830.98	39° 59′ 37.355 N	109° 23' 5.12
4,513.00	0.75	238.22	4,444.91	183.42	606.07	14,527,852.60	2,092,829.93	39° 59′ 37.351 N	109° 23' 5.13
4,603.00	0.84	228.06	4,534.90	182.67	605.08	14,527,851.83	2,092,828.95	39° 59′ 37.343 N	109° 23' 5.15
4,694.00	0.53	211.35	4,625.90	181.86	604.36	14,527,851.02	2,092,828.25	39° 59′ 37.335 N	109° 23' 5.16
4,784.00 4,875.00	0.70 1.37	200.63	4,715.89	180.99	603.95	14,527,850.14	2,092,827.85	39° 59′ 37.327 N	109° 23' 5.16
4,965.00	1.37 0.30	194.50 135.01	4,806.87	179.42	603.48	14,527,848.56	2,092,827.41	39° 59' 37.311 N	109° 23' 5.17
5,056.00		135.01	4,896.86 4,887.86	178.21	603.38	14,527,847.35	2,092,827.33	39° 59′ 37.299 N	109° 23' 5.17
5,056.00	1.32	49.90 51.67	4,987.86	178.72	604.35	14,527,847.87	2,092,828.29	39° 59′ 37.304 N	109° 23' 5.16
5,146.00	1.49 0.85	51.67 69.14	5,077.83 5,168.81	180.11	606.06	14,527,849.30	2,092,829.98	39° 59′ 37.318 N	109° 23' 5.13
5,327.00	1.24	69.14 76.77	5,168.81 5,258.70	181.08 181.55	607.62	14,527,850.30	2,092,831.52	39° 59′ 37.328 N	109° 23' 5.11
5,327.00	1.24	76.77 103.56	5,258.79 5,349.77	181.55	609.19	14,527,850.79	2,092,833.08	39° 59′ 37.332 N	109° 23' 5.09
5,508.00	1.33	103.56	5,349.77 5,439.75	181.52	611.18	14,527,850.80	2,092,835.07	39° 59' 37.332 N	109° 23′ 5.07
5,599.00	1.06	123.55	5,530.73	181.05 180.35	613.20 614.91	14,527,850.36 14,527,849.70	2,092,837.10 2,092,838.82	39° 59′ 37.327 N 39° 59′ 37.321 N	109° 23' 5.04



## **SDI**Survey Report - Geographic



Company:

Kerr McGee Oil and Gas Onshore LP

Project: Site: Uintah County, UT UTM12 NBU 922-36G3 PAD

Well: NBU 922-36G4BS

Wellbore: Design: OH OH Local Co-ordinate Reference:

TVD Reference:

MD Reference: North Reference:

North Reference: Survey Calculation Method:

Database:

Well NBU 922-36G4BS

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139)

GL 4958' & KB 14' @ 4972.00ft (ENSIGN 139) True

Minimum Curvature

EDM 5000.1 Single User Db

Measured			Vertical			Map	Map		
Depth	Inclination	Azimuth	Depth	+N/-S	+E/-W	Northing	Easting		
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(usft)	(usft)	Latitude	Longitude
5,689.00	1.47	133.51	5,620.71	179.10	616.44	14,527,848.47	2,092,840.38	39° 59' 37.308 N	109° 23' 5.005 \
5,780.00	0.26	80.22	5,711.70	178.33	617. <b>49</b>	14,527,847.72	2,092,841.44	39° 59′ 37.301 N	109° 23' 4,991
5,870.00	0.47	345.93	5,801.70	178.72	617.60	14,527,848.12	2,092,841.54	39° 59′ 37.304 N	109° 23' 4.990
5,961.00	0.65	344.25	5,892.69	179.58	617.37	14,527,848.97	2,092,841.30	39° 59′ 37.313 N	109° 23' 4.993
6,051.00	0.83	338.74	5,982.68	180.68	617.00	14,527,850.06	2,092,840,90	39° 59' 37,324 N	109° 23' 4.998
6,142.00	0.43	350.94	6,073.68	181.63	616.71	14,527,851.01	2,092,840.59	39° 59' 37,333 N	109° 23' 5.002
6,232.00	0.09	348.55	6,163.68	182.03	616.64	14,527,851.41	2,092,840.52	39° 59' 37.337 N	109° 23' 5.002
6,323.00	0.79	<b>338</b> ,97	6,254.67	182.69	616.40	14,527,852.06	2,092,840.27	39° 59' 37.344 N	109° 23' 5.006
6,413.00	1.04	346.20	6,344.66	184.06	615.98	14,527,853.43	2,092,839.83	39° 59' 37.357 N	109° 23' 5.011
6,504.00	0.77	333,12	6,435.65	185.41	615.51	14,527,854.77	2,092,839.33	39° 59' 37.371 N	109° 23' 5.017
6,594.00	0.35	357.34	6,525.65	186.22	615.22	14,527,855.57	2,092,839.03	39° 59' 37.379 N	109° 23' 5.021
6,685.00	0.67	8.25	6,616.64	187.03	615.29	14,527,856.38	2,092,839.08	39° 59′ 37.387 N	109° 23' 5.020
6,775.00	0.32	95.46	6,706.64	187.52	615.61	14,527,856.88	2,092,839.39	39° 59′ 37.391 N	109° 23' 5.016
6,866.00	0.59	135.91	6,797.64	187.16	616.19	14,527,856.53	2,092,839,98	39° 59' 37.388 N	109° 23' 5.008
6,956.00	0.71	154.79	6,887.63	186.33	616.75	14,527,855.70	2,092,840.55	39° 59′ 37.380 N	109° 23' 5.001
7,047.00	0.89	139.59	6,978.62	185.28	617.45	14,527,854.67	2,092,841.27	39° 59' 37.369 N	109° 23' 4.992
7,138.00	1.55	169.88	7,069.60	183.53	618.12	14,527,852.93	2,092,841.98	39° 59' 37.352 N	109° 23' 4.983
7,228.00	0.47	231.29	7,159.59	182.10	618.05	14,527,851.50	2.092,841.93	39° 59' 37.338 N	109° 23' 4.984
7,319.00	0.53	198.08	7,250.59	181.47	617.63	14,527,850.86	2,092,841.52	39° 59' 37.332 N	109° 23' 4.990
7,409.00	0.69	172.03	7,340.58	180.53	617.57	14,527,849.93	2,092,841.48	39° 59' 37.322 N	109° 23' 4.990
7,500.00	1.06	181.29	7,431.57	179.15	617.63	14,527,848,54	2,092,841.56	39° 59' 37,309 N	109° 23' 4.990
7,590.00	0.50	232,20	7,521.56	178.08	617.30	14,527,847.47	2,092,841.25	39° 59' 37,298 N	109° 23' 4.994
7,680.00	0.95	319.44	7,611.56	178.40	616.51	14,527,847.78	2,092,840.45	39° 59′ 37.301 N	109° 23' 5.004
7,771.00	0.71	326.22	7,702.55	179.44	615.70	14,527,848.80	2,092,839.63	39° 59' 37.312 N	109° 23' 5.014
7,862.00	0.44	332.11	7,793.54	180.22	615.22	14,527,849.57	2,092,839.14	39° 59' 37.319 N	109° 23' 5.021
7,952.00	0.32	111.75	7,883.54	180.43	615.30	14,527,849.79	2,092,839.21	39° 59' 37,321 N	109° 23' 5.020
8,042.00	0.51	74.01	7,973.54	180.45	615.91	14,527,849.82	2,092,839.82	39° 59' 37.322 N	109° 23' 5.012
8,133.00	0.74	80.39	8,064.53	180.66	616.88	14,527,850.04	2,092,840.79	39° 59' 37.324 N	109° 23' 4.999
8,224.00	1.06	133.48	8,155.52	180.18	618,07	14,527,849.58	2.092,841.99	39° 59' 37.319 N	109° 23' 4.984
8,314.00	1.11	145.72	8,245.51	178.89	619.17	14,527,848.31	2,092,843.11	39° 59' 37.306 N	109° 23' 4.970
8,405.00	1.38	140.49	8,336.49	177.31	620.36	14,527,846.76	2,092,844.33	39° 59′ 37.291 N	109° 23' 4.955
8,495.00	1.43	130.45	8,426.46	175.75	621.91	14,527,845.22	2,092,845.90	39° 59' 37.275 N	109 23 4.935 109° 23' 4.935
8,586.00	1.06	143.94	8,517.44	174.33	623.27	14,527,843.83	2,092,847.28	39° 59' 37.261 N	109 23 4.935 109° 23' 4.917
8,676.00	1.49	135.59	8,607.42	172,82	624.57	14,527,842.34	2,092,848.62	39° 59' 37.246 N	109 23 4.917 109° 23' 4.900
8,716.00	1.48	127.33	8,647.40	172.14	625.35	14,527,841.67	2,092,849.41	39° 59' 37.239 N	109° 23' 4.891
LAST SE	MWD PROD					. 1,027,047.07	2,002,070.71	00 00 01.200 N	108 23 4.881
8,770.00	1.48	127.33	8,701.38	171.29	626.46	14,527,840.85	2,092,850.53	39° 59' 37,231 N	109° 23' 4.876

Design Annotations	n de la companya de La companya de la co	the management of the manageme	and the second	
Measured Depth (ft)	Vertical Depth (ft)	Local Coord +N/-S (ft)	dinates +E/-W (ft)	Comment
191.00	191.00	0.03	0.58	FIRST SDI MWD SURFACE SURVEY
2,430.00	2,378.01	138.70	430.77	LAST SDI MWD SURFACE SURVEY
2,575.00	2,518.80	148.96	463.88	FIRST SDI MWD PRODUCTION SURVEY
8,716.00	8,647.40	172.14	625.35	LAST SDI MWD PRODUCTION SURVEY
8,770.00	8,701.38	171.29	626. <b>46</b>	SDI PROJECTION TO BIT

Checked By:	Approved By:	Date	·
		2000	